

SURVEY & REMONUMENTATION

OCT 23 1998

GLADWIN County Remonumentation

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER **001** PAGE **244**

For corners in

_____ <u>GLADWIN</u> _____	Located in:	Corner Code # _____
(County)		
1. Public Land Survey	T18N R02E	B-7
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling	S _____ T _____ R _____	_____
in Section	S _____ T _____ R _____	_____
3. Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

STATE OF MICHIGAN
GLADWIN COUNTY
FILED-CORNER

13 OCT 1998 12:51:49 PM

BONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Mark R Robison, in a field survey on June, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:
B-7: 1846 John Mullett Set 1/4 Section Post
 Wit-(1)Beech 10 N76E 36
 (2)Hemlock 10 S87W 30

 1992-97 DNR survey & LCRC#367
 Set DNR Mon & Cedar Post
 Wit-(3)3" Maple N80W 6.8
 (4)2" Oak North 33.3
 (5)6" Maple S70E 22.40
 (6)3" Maple S15E 3.4

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
B-7: Accepted DNR corner. Corner agrees with witnesses (3), (4), (5) & (6), blazes only, as recorded on LCRC#367.
 See dossier and LCRC#367 for additional information.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
B-7: Corner common to Sections 18 & 19. Accepted found DNR Monument and Post, left in place.

Witnesses:
 North 2" Oak, nail & tag, 33.3'
 S70E 6" Maple, nail & tag, 22.65'
 S15E 3" Maple, nail & tag, 3.45'
 N85W 3" Maple, nail & tag, 19.91'

APPROVED LAND CORNER
 P.A. 345 of 1990
 Gladwin County

Co. Rep. [Signature]
 Date 8/11/98

Signed by [Signature]
 Surveyor's Michigan License No. 27458



Date 10-5-98