

SURVEY & REMONUMENTATION

OCT 23 1998

GLADWIN County Remonumentation

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 246

For corners in

<u>GLADWIN</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T18N R02E	C-4
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
GLADWIN COUNTY
FILED-CORNER

13 OCT 1998 12:52:15 PM

BONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Mark R Robison, in a field survey on April, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mention in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate

A. Description of original monument and accessories and/or subsequent restoration:

C-4: 1846 John Mullett Set 1/4 Sec Post Found 1/2 roerod
 Wit-(1)Hemlock 10 N77E 38 Wit-(6)26" R. Pine N87W 31.20
 (2)Do 10 N85W 31 (7)19" R. Pine N60W 28.35
 1967 Edmands Engineering partial survey (8)8" R. Pine N40E 31.65
 1972 Lapham (work dwg & wit) Set Iron (9)Found 1/2" roerod in mon box in
 Wit-(3)N55W 14" R. Pine 28.35 center M-61 South 50.76
 (4)N89W 20" R. Pine 31.20 1996 Lapham survey & LCRC#406
 (5)N40E 3" R. Pine 31.65 Found C.I.
 Wit-same as (4),(5)&(6)
 1992-97 DNR survey & LCRC#432 1997 Claypool LCRC#443 Found C.I.
 Wit-(10)West 9.196m 19mm rod in

800mm Pine
(11)N50W 8.638m 600mm Pine
(12)N30W 15.609m to 500mm Pine
(13)N20E 9.620m 250mm Pine

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-4: Found 1/2" roerod set by DNR in large retracement survey of See dossier & LCRC#432 for additional information.
T18N, R2E. This corner was reset by DNR in 1972 from witnesses of survey by J. Meyers P.S.#14099. Corner agrees with witnesses (3), (5), (6) & (7). Monument Box in centerline of M-61 set by MDOT is not acceptable.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-4: Corner common to Sections 7 & 8. Set 5/8" x 36" roerod in place of found 1/2" rod with Gladwin County Remonumentation cap marked P.S.#14099.

Witnesses:
South 1/2" iron in Monument Box 50.76'
N40E 6" Red Pine, nail & tag, 31.60'
N55W 16" Red Pine, nail & tag, 28.38'
N89W 24" Red Pine, iron in base 30.15'
N40W 14" Red Pine, nail & tag, 90.50'
N46E 12" Maple, nail & tag, 58.05'

APPROVED LAND CORNER

P.A. 345 of 1990
Gladwin County

Co Rep. J. Meyers
Date 8/11/98

Signed by Mark R Robison
Surveyor's Michigan License No. 27458



Date 10-5-98