

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
GLADWIN

(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>18N</u> R <u>2E</u>	<u>I-5, I-6,</u>
	T _____ R _____	<u>I-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>15</u> T _____ R _____	<u>7</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	8	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, C.T. KIISKILA, in a field survey on JULY 28, 19 94
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(NO CONCLUSIVE EVIDENCE OF G.L.O. CORNER MONUMENT, CORNER BT'S, LINE TREES, TOPOGRAPHY, ETC. AS CALLED OUT IN THE G.L.O. LINE NOTES; UNLESS NOTED IN ITEM "B" BELOW.)



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

<u>I-5</u> FD 1/2" REROD FOR NE COR S-15 AS SET BY J. MEYERS, PS#14099 IN 1982. COR IS IN CTR N-S GRAVEL RD & 40' SOUTH OF CTR E-W TRAIL.	<u>I-6</u> FD REROD FOR E 1/4 COR S-15 AS SET BY P.S. J. MEYERS IN 1982. COR IS IN CTR OF N-S GRAVEL RD & 35' N OF TRAIL TO EAST.	<u>I-7</u> ACCEPTED FD 1/2" REROD W/ BATTERED PS CAP FOR NW COR S-23. IRON SET BY J. MEYERS, P.S.#14099, IN 1976 (CERT. OF SUR. ORDER #760865), P. LAPHAM RECORDED COR I-6-77, P. 154 OF L.C.R.C'S; ALSO RECORDED BY J. MEYERS, P. 260 OF L.C.R.C'S. TRUE LINE CUT WEST.	<u>7</u> SET N 1/8 COR ON EAST LINE OF SEC 15 PER STANDARD BLM INSTRUCTIONS. COR FALLS IN CTR N-S GRAVEL ROAD.
--	--	---	---

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<u>I-5</u> FD BENT REROD. REPL'D W/ 1/2" X 24" REROD. 6" J PINE N68°W 26.37' 5" J PINE S69°W 23.85' #12" OAK S74°E 28.08' 11" J PINE N32°E 52.20' SET CED POST EAST 33.02' #J. MEYERS MIT.	<u>I-6</u> FD 1/2" REROD. #16" TN OAK N70°W 32.78' #10" J PINE N57°E 27.58' SET CED POST S84°E 33.48' 4" J PINE S57°W 28.95' FD 1 1/2" PIPE EAST 33.23' #J. MEYERS 1982 MIT.	<u>I-7</u> FD 1/2" REROD (REPL'D W/ 5/8" X 3/4" REROD WITH PS CAP) IN CTR N-S GRAVEL RD & 6" DEEP. #12" OAK S45°E 53.52' 14" OAK N69°W 35.55' #10" OAK N26°W 45.23' #14-16" TN OAK S85°E 31.09' SET CED POST W/LOC TAG (BESIDE FD IR W/PS CAP #14469 L.UBANIAK) WEST 33.11'	<u>7</u> SET 5/8" X 3/4" REROD W/CAP (0.8' DEEP). 14" OAK S68°E 28.28' 6" R PINE S65°W 25.44' 5" J PINE N28°W 52.53' SET CED POST EAST 32.81' 8" J PINE N58°E 31.99'
---	---	---	--

Signed by Carl T Kiiskila Date 3-28-97
 Surveyor's Michigan License No. 33981