

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
**GLADWIN**

(County)

Located In:

Corner Code ~~##~~

1. Public Land Survey	T <u>18N</u> R <u>2E</u>	<u>F-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>16</u> T _____ R _____	<u>9, 13, 16</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, C. T. KIISKILA, in a field survey on JULY 25, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-7	9	13
(NO CONCLUSIVE EVIDENCE OF G.L.O. CORNER MONUMENT, CORNER BT'S, LINE TREES, TOPOGRAPHY, ETC. AS CALLED OUT IN THE G.L.O. LINE NOTES; UNLESS NOTED IN ITEM "B" BELOW.)		



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-7	9	13	16
REESTABLISHED S 1/4 COR S-16 MIDWAY AND ON LINE BETWEEN REESTAB'D SE & SW COR S-16. OLD HAD 2 W.PINE STUMPS IN AREA BUT NOTHING CONCLUSIVE FOUND. COR FITS P.S. J.MEYERS, S-16 SUBDIVISION. COR IN LOWLAND HEDGS IN 6" WATER, APPEARS TO BE S'LY EDGE BEAVER POND. THERE IS A WINDING TRAIL 177' (± 6') SOUTH.	ACCEPTED P.S. J.MEYERS IRON FOR NE COR OF NW 1/4 OF SE 1/4 OF S-16. PER J.M. CERT OF SURVEY ORDER NO. 6-866617, DATED SEPT. 17, 1986.	ESTABLISHED CENTER OF SE 1/4 SEC 16 PER STANDARD BLM INSTRUCTIONS. 3'-4' WIDE DRAINAGE COURSE FLOWING S'LY IS 44' ± 2' WEST. COR FITS P.S. J.MEYERS SEC 16 SEC. SUBDIVISION.	ESTABLISHED SW COR OF SE 1/4 OF SE 1/4 OF SEC 16 PER STANDARD BLM INSTRUCTIONS. CENTER E-W TRAIL IS 192' (± 3') SOUTH.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-7	9	13	16
SET BNR MON & CED POST.	FD 1/2" REROD W/RLS CAP. ADDED LOC TAG TO FD CED POST.	DROVE 1" X 54" GALV PIPE W/RLS CAP. SET CED POST W/LOC TAG.	DROVE 1" X 60" GALV PIPE W/RLS CAP. SET CED POST W/LOC TAG.
7" MAPLE CLUMP N30°W 27.6'	13" B OAK N20°W 36.7'	10" MAPLE N60°W 15.2'	4" J PINE N25°W 3.0'
6" MAPLE CLP3 NORTH 20.0'	20" R PINE N30°E 106.9'	3" B ASH N10°E 4.6'	6" J PINE EAST 5.2'
12" MAPLE CLP3 N65°E 27.3'	7" MAPLE N65°E 53.7'	30" W PINE N65°E 30.3'	5" J PINE S20°E 15.9'
12" MAPLE N85°W 9.7'	11" TRPL MAPLE S55°E 43.3'	30" W PINE S60°E 25.6'	6" J PINE S85°W 8.6'

Signed by Carl T. Kiiskila Date 3-28-97  
 Surveyor's Michigan License No. 33981