

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in ELAMIN Located In: _____ Corner Code # _____
 (County)

1. Public Land Survey T 18N R 2E A-8, B-9
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S 30 T _____ R _____
 In Section S 19 T _____ R _____
 3. Miscellaneous S _____ T _____ R _____
 Property in Section S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

I, C.T. KIISKILA, in a field survey on NOVEMBER 9, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-8 B-9 1 10

(NO CONCLUSIVE EVIDENCE OF G.L.O. CORNER MONUMENT, CORNER BT'S, LINE TREES, TOPOGRAPHY, ETC. AS CALLED OUT IN THE G.L.O. LINE NOTES; UNLESS NOTED IN ITEM "B" BELOW.)

("B" CONT.):
 AN SP POSITION WOULD FALL SOME 45' SOUTH OF FOUND IRON. FOR LACK OF BETTER EVIDENCE, ACCEPTED IRON AS FOUND.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-8 B-9 1 10

FD & ACCEPTED 1" GALV PIPE FOR NW 1/4 COR SEC 19. NOW IS P.S. P. LAPMAN & P.S. H. FLUWARTY COR OF RECORD. COR FITS P.S. J. MEYERS SUBDIVISION OF S-24, T18N-R1E. COR IS IN APPROX CTR OF OLD ABANDONED N-S ROAD GRADE. NORTH EDGE OF RIVER IS 120' (± 2') SOUTH.

FD & ACCEPTED 1/2" REROD OF UNKNOWN ORIGIN FOR S 1/4 COR S-19. THERE IS AN APPROX 2" DEFL. IN THE S LINE OF S-9 AT THIS POINT & THE SEC LINE RUNS DOWN CTR OF GRVL RD TO E & W. CTR OF 28' WIDE E-W GRVL RD IS 3' S. SAME DEFL IN THE SEC LINE IS ALSO FD AT THE N 1/4 COR S-18 (COR B-5). COR DOES FIT PRORATED DIST TO OLD RUN OUT ON S LINE S-19. (CONT)

ESTABLISHED THE NE COR OF FRL NW 1/4 OF FRL NW 1/4 OF S-30 PER STANDARD BLM INSTRUCTIONS. CTR OF E-W GRAVEL ROAD IS 3' NORTH.

ESTABLISHED NW COR OF SW 1/4 OF SW 1/4 OF SEC 19 PER STANDARD BLM INSTRUCTIONS. CORNER FALLS IN APPROX CENTER N-S GRAVEL ROAD.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-8 B-9 1 10

FD 1" GALV PIPE. ADDED CED POST W/LOC TAG.

FD 1/2" REROD. REPLACED WITH 5/8" X 34" REROD W/PS CAP.

BROVE 5/8" X 34" REROD W/PS CAP.

BR 5/8" X 34" REROD W/PS CAP.

5" ELM N45°W 14.19'
 110° TN MAPLE S90°E 23.83'
 116° MAPLE S55°E 26.13'
 111° TRPL MAPLE S45°W 39.08'

7" ELM N40°E 52.19'
 2" ASH S15°E 60.33'
 6" ASH S45°W 79.94'
 SET CED POST W/
 LOC TAG SOUTH 33'

9" TN MAPLE N15°W 59.58'
 4" ASH N35°E 50.82'
 8" TN MAPLE S03°E 51.93'
 6" MAPLE S35°W 61.45'
 SET CED POST W/
 LOC TAG SOUTH 33'

FD 5" DIA CONC MON WEST 31.71'
 12" MAPLE N45°W 65.35'
 8" MAPLE CLP4 S70°E 78.52'
 POWER POLE S50°W 38.40'
 SET CED POST W/
 LOC TAG EAST 33'

By P.S. H. FLUWARTY 1970 WIT.
 Signed by Carl T. Kiiskila Date 3-28-97

