

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
GLADWIN
 (County)

Located In: _____ Corner Code =# _____

- | | | |
|------------------------------------|-------------------------|---------------|
| 1. Public Land Survey | T 18N R 2E | C-5, C-6, C-7 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S 18 T _____ R _____ | 2 |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, C.F. ROSE, in a field survey on SEPT. 15, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(NO EVIDENCE OF G.L.O. CORNER, B.T.'S, LINE TREES & TOPOGRAPHY, AS CALLED OUT IN THE G.L.O. LINE NOTES; UNLESS NOTED IN ITEM "B" BELOW.)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- | | | | |
|---|--|---|---|
| C-5 FD AND ACCEPTED OLD 3/8" IRON ROD FOR NE COR OF SEC 18. ROD FALLS IN APPROX CTR OF 24'± WIDE N-S GR. RD; CTR OF GR RD LOOKING N IS 3'± NORTH. CORNER AS FD FITS PRIOR SUR BY PS, J. MEYERS; LARGE RETRACEMENT SURVEY NUMBERS (SEE COPY OF HIS WORKING DWG) FOR 2-MI S, 1-MI N, 1-MI W AND 3-MI E. | C-6 REESTAB. E 1/4 COR OF S-18 MIDWAY BETWEEN SEC COR'S TO N & S AND IN CTR OF OLD N-S TWP ROAD GRADE (NOW ON COUNTY RD SYSTEM). | C-7 RESTORED SE COR SEC 18 BY PROPORTIONATE MEAS BTWN FD NE S-18 & FD E 1/4 S-19 AND IN CTR OF OLD N-S TWP RD (NOW ON CO RD SYSTEM). APPROX CTR OF 72" CROSS CULV, UNDER 10'± FILL, IS 23' S. COR AS RESTORED BY THIS METHOD FITS PRIOR SURVEY BY PS, J. MEYERS; SEE HIS LARGE RETRACEMENT SURVEY IN THIS AREA; (COPY IN OUR SUR FILE). | 2 ESTAB. E 1/8 COR ON N. LINE OF SEC 18 (NW COR OF NE 1/4 OF NE 1/4 OF S-18) EQUIDISTANT & ON LINE BETWEEN THE N 1/4 COR & NE COR OF S-18. COR FALLS IN APPROX. CTR OF 20' WIDE E-W GRAVEL RD. A FN COR (CED POST, B-W, M & S) IS 25'-S AND 2'-W. ALSO; AN OLD FN COR (CED POST, B-W, M & N) IS 32'-N & 15' W. ALSO SEE COR B-5, 1/4 COR TO SEC'S 7 & 18. |
|---|--|---|---|

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | | | |
|---|---|--|--|
| C-5 DROVE 1"x 36" GALV. PIPE W/PS CAP OVER FD OLD 3/8" IRON ROD 15" R. PINE S85°E 53.2' 20" OAK N60°E 60.0' 2" MAPLE N25°W 85.6' 2" B. CHERRY S65°W 67.5' | C-6 DROVE 5/8"x 34" REROD W/PS CAP. 3" B. CHERRY (CLP) N45°W 58.7' 7" TAMARACK N85°E 79.8' 6" MAPLE S65°E 49.0' FD 7/8" SOLID IRON ROD S00°29'W 56.36' SET CEDAR POST WITH LOCATION TAG WEST 33' | C-7 DROVE 5/8"x 34" REROD W/PS CAP 10" ASH N20°W 86.9' TOP CTR E END 72" CMP S50°E 37.7' TOP CTR W END 72" CMP S60°W 42.6' FD 7/8" SOLID IRON ROD S06°53'W 8.87' SET CEDAR POST W/LOCATION TAG WEST 18' | 2 DROVE 5/8"x 34" REROD W/PS CAP 5" MAPLE S40°E 44.69' 5" B. OAK S10°E 38.25' 3" R. PINE S40°W 34.24' DROVE 5/8"x 34" REROD W/PS CAP & SET CED POST. S00°02'W 33.00' DROVE 5/8"x 34" REROD W/PS CAP & SET CEDAR POST W/LOC TAG. N00°01'E 33.00' |
|---|---|--|--|

Signed by Carl F. Roser Date 12-14-94

Surveyor's Michigan License No. 12028

