

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
**GLADWIN**

(County)	Located In:	Corner Code #:
1. Public Land Survey	T 18N R 2E	A-4
	T R	
	T R	
	T R	
2. Property Controlling in Section	S 7 T R	10
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat		
5. Private Claims _____		

**Register of Deeds Stamp & File Number**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	8	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, CARL T. KIISKILA, in a field survey on JANUARY 27, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

A-4	10
U.S. G.L.D. - SET OR. SECTION POST: W.PINE 18 IN N72°W	
12LKS. W.PINE 8 IN S52 1/2°W 15LKS. NO SIGN OF POST OR WIT.	



**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

A-4	10
FD 1 1/2" PIPE IN 6" SQUARE CONC. BLOCK FOR NW1/4 COR S-7. CORNER PROBABLY SET BY MARCUS SCHAAF, CONSERVATION DEPT. FORESTER AND SURVEYOR IN 1930'S+/- (NO RECORDS). CORNER FITS OTHER MONUMENTATION FB ALONG TWP. LINE FOR 1 1/2 MILES TO NORTH AND 1/2 MILE SOUTH. CTR OF M-61 IS 54.4' NORTH. ROM OF OLD CEDAR POSTS TO SOUTH IS 21' WEST.	FOUND 1 1/2" PIPE IN 6" SQ. x 6" DEEP CONC. BLOCK FOR SW COR OF NW1/4 OF SW1/4 OF S-7. CORNER PROBABLY SET BY MARCUS SCHAAF, CONSERVATION DEPT. SURVEYOR & FORESTER, AROUND 1935+/- . CORNER OF OLD WOVEN WIRE FN TO EAST & SOUTH IS 28'+/- NORTH & 28'+/- EAST.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

A-4	10
SET 1"x 3/8" GALV. PIPE W/4" ALUMN DNR CAP IN PLACE OF FOUND SHORT PIPE IN CONC. BLOCK. DROVE BLUE CARSONITE POST. CTR OF MON BOX COVER IN CTR M-61 N20 36'W 58.70'	FD SHORT PIPE IN CONC. BLOCK. DROVE 1"x 60" GALV. PIPE W/PS CAP & SET CARSONITE POST W/LOC TAG.
18" TRI.OAK N02°W 157.34' (DROVE SPIKE & TAG E. SIDE)	5" SOFT MAPLE N33°W 19.22' (DROVE SPIKE & TAG SW SIDE)
8" D.CHERRY S65°E 91.60' (DROVE SPIKE & TAG NE SIDE)	5" SOFT MAPLE N54°E 37.66' (DROVE SPIKE & TAG SE SIDE)
16" SOFT MAPLE DUE S. 171.13' (DROVE SPIKE & TAG E SIDE)	6" SOFT MAPLE (CLP 4) S06°E 21.86' (DROVE NAIL & TAG N SIDE)
4" OAK S35°W 102.15' (DROVE SPIKE & TAG)	9" W.PINE S02°W 47.52' (DROVE SPIKE & TAG E SIDE)

Signed by Carl T. Kiiskila Date 4-7-97

Surveyor's Michigan License No. 33981