

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
GLADWIN
 (County)

Located In:

Corner Code ~~74~~

- | | | | | | |
|---------------------------------------|---|-----|---|----|----------|
| 1. Public Land Survey | T | 18N | R | 2E | A-1, A-2 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | T | R | | |
| | S | T | R | | |
| 3. Miscellaneous Property in Sec. | S | T | R | | |
| | S | T | R | | |
| 4. Lot No. _____, Recorded Plat _____ | | | | | |
| 5. Private Claims _____ | | | | | |

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, CARL T. KIISKILA, in a field survey on JANUARY 2, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules theretofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-1
 U.S. G.L.O. - N.ASH 6 IN S22°W 16LKS, FIR 5 IN S72°W 27LKS, B.ASH 9 IN N17 1/2°W 74LKS. US CALLED FOR COR IN SWAMP & 1-CHAIN NORTH TO LEAVE SWAMP. WE FIND COR IN SWAMP, NEAR NE EDGE & 70' +/- 15' NORTH TO LEAVE SWAMP. ALSO US MEAS WEST AT "6.00 TOUCHED SWAMP ON RIGHT", LOOKING WEST RUNS DOWN EDGE OF SWAMP.

A-2
 U.S. G.L.O. - SET OR. SECTION POST, S.MAPLE 12 IN N51°W 26LKS, S.MAPLE 5 IN N42°E 25LKS. NO SIGN OF GOVT POST OR MK.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-1
 FD OLD RUSTY 1 1/2" PIPE W/TOP BROKE OFF FOR 4-TWP CORNER. CORNER PROBABLY SET BY CONSERVATION DEPT. FORESTER & SURVEYOR MARCUS SCHAAF. COR FITS GLO SWAMP CALLS. ACCEPT COR AS BEST EVIDENCE OF RESTORATION OF US GLO POSITION FOR 4-TWP. CORNER.

A-2
 FD 1 1/2" PIPE PROBABLY SET BY MARCUS SCHAAF, CONSERVATION DEPT. FORESTER & SURVEYOR (1910'S TO 1940'S) FOR W1/4 COR S-6. SMALL BROOK C-SW'LY IS 274' +/- 4' SOUTH; US-GLO CROSS BROOK COURSE SW 297' SOUTH. ACCEPT AS BEST POSITION FOR RESTORATION OF W1/4 COR S-6.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-1
 FD 1 1/2" PIPE REPLACED W/1"x 72" GALV. PIPE W/4" ALUMN DNR CAP. DROVE BLUE CARSONITE POST.

15" MAPLE	N87°W	39.08' (DROVE SPIKE & TAG S SIDE)
6" MAPLE	N45°W	45.52' (DROVE SPIKE & TAG SW SIDE)
6" B.ASH	N58°E	18.41' (DROVE SPIKE & TAG)
7" MAPLE	S18°E	54.18' (DROVE SPIKE & TAG)
6" MAPLE	S30°W	9.30' (DROVE SPIKE & TAG NW SIDE)

A-2
 SET 1"x 3/8" PIPE W/4" ALUMN DNR CAP IN PLACE OF FD OLD 1 1/2" IRON PIPE. DROVE BLUE CARSONITE POST.

12" MAPLE	N15°W	18.40' (DROVE SPIKE & TAG E SIDE)
12" MAPLE	N85°E	16.30' (DROVE SPIKE & TAG S SIDE)
12" MAPLE	S45°E	19.26' (DROVE SPIKE & TAG NE SIDE)
8" TW.MAPLE	S33°W	3.94' (DROVE SPIKE & TAG SE SIDE)

Signed by Carl T. Kiiskila 33981

Date 4-7-97

Surveyor's Michigan License No. _____