

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
GLADWIN
 (County)

Located In: _____ Corner Code: 11

- | | | |
|---------------------------------------|----------------------------|------------|
| 1. Public Land Survey | T <u>18N</u> R <u>2E</u> | <u>B-4</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S <u>7</u> T _____ R _____ | <u>8</u> |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Register of Deeds Stamp & File Number

I, CARL T. KIISKILA, in a field survey on JANUARY 8, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
B-4 8



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
B-4 8
 ESTABLISHED THE CTR OF S-7 AT INTER. OF 1/4 LINES. FENCE TO EAST IS 43' SOUTH. FENCE CORNER, FN W & S, IS 36' WEST & 76' SOUTH.
 ESTABLISHED THE NE COR OF NW1/4 OF SW1/4 OF S-7 PER STANDARD BLM INSTRUCTIONS. OLD CORNER FN POST, B/WIRE ON CEDAR POSTS TO S & E, IS 51' SOUTH & 48' WEST.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
B-4 8
 DROVE SHORT PK, 1 1/2' SOUTH OF CTR OF M-61.
 4" W.PINE S68°W 138.38' (DROVE SPIKE & TAG NW SIDE)
 14" W.PINE S50°W 83.55' (DROVE SPIKE & TAG NW SIDE)
 7" W.PINE S20°W 120.22' (DROVE SPIKE & TAG E SIDE)
 N. EDGE BRIDGE NB2°W 138.3' (E. END CONC. WALL)
 DROVE 5/8"x 3/4" REROD W/PS CAP & BLUE CARSONITE POST WITH LOCATION TAG NORTH 74.21'
 DROVE 5/8"x 3/4" REROD W/PS CAP.
 9" W.PINE S65°E 94.88' (DROVE SPIKE & TAG SW SIDE)
 13" W.PINE S27°W 48.36' (DROVE SPIKE & TAG E SIDE)
 7" ASH S60°W 93.24' (DROVE SPIKE & TAG SE SIDE)
 DROVE 5/8"x 3/4" REROD W/PS CAP & BLUE CARSONITE POST WITH LOCATION TAG S00°10'E 51.05'
 CTR. M-61 NORTH 22.4'

Signed by Carl T. Kiiskila Date 4-7-97
 Surveyor's Michigan License No. 33981