

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
GLADWIN
 (County)

Located In: Corner Code #

- | | | | | | |
|---------------------------------------|---|-----|---|----|-----|
| 1. Public Land Survey | T | 18N | R | 2E | C-4 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | 7 | T | R | 9 |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |
| 4. Lot No. _____, Recorded Plat _____ | | | | | |
| 5. Private Claims _____ | | | | | |

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, CARL T. KIISKILA, in a field survey on JANUARY 28, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 C-4 9

U.S. G.L.O. - SET OR. SECTION POST; HEMLOCK 10 N77°E 38, HEMLOCK 10 N85°W 31. NO SIGN OF GLO POST OR WIT.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 C-4 9

FD AND ACCEPTED 1/2" REROD FOR 1/4 COR SEC. 8 (FD REROD LEANING AND RESET IRON PER 3-NIT'S FOUND IN J.MEYERS SURVEY NOTES). FD H.SCHAAF CONC MON 4.9' +/- NORTH AND 0.7' WEST, DID NOT ACCEPT IT FOR 1/4 COR. CTR OF M-61 IS 52' SOUTH.

ESTABLISHED THE NW COR OF E1/2 OF SE1/4 OF 5-7 PER STANDARD BLM INSTRUCTIONS.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 C-4 9

FD 1/2" REROD.
 †26° R.PINE N87°W 31.20'
 †19° R.PINE N60°W 28.35'
 †8° R.PINE N40°E 31.65'
 FD 1/2" REROD IN MON BOX (IN CTR M-61) SOUTH 50.76'
 SET CEBAP POST W/LDC TAG EAST 33'

DROVE 5/8" x 34" REROD W/PS CAP.
 8° SOFT MAPLE N53°W 79.25' (DROVE SPIKE & TAG NE SIDE)
 7° R.PINE N47°E 86.17' (DROVE SPIKE & TAG SE SIDE)
 CTR 28' WIDE M-61 SOUTH 26'
 SET BLUE CARSONITE POST W/LDC TAG E SIDE OF FD. 1/2" IRON W/PS CAP †27458 500°04'E 100.81'

† = PS J.MEYERS WITS.

Signed by Carl T. Kiiskila Date 4-7-97
 Surveyor's Michigan License No. 33981