

GLADWIN COUNTY REMONUMENTATION

LIBER 001 PAGE 168

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
GLADWIN COUNTY  
FILED - Remonumentation

For corners in

GLADWIN (County)	Located In:	Corner Code #
1. Public Land Survey	T 18N R 1W	B-3
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

17 OCT 97 1:19 P.M.

BONNIE K. HOUSE  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, MARK R. ROBISON, in a field survey on May 22, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3		●											
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1877 T. Gale Merrill Set Post  
Wit.-(1)S40E 9 links 11" Birch  
(2)N34W 30 links 4" Cedar
  - 1990 Lapham survey & working dwg  
Found R/R spike  
Wit.-same as (3)&(4)
  - 1992 Lapham survey & working dwg
  - 1985 Lapham working dwg & field notes  
Set R.R. spike  
(Corner set from Edmands Eng. Railroad  
R/W maps and old survey of airport.)  
Wit.-(3)S.W. Runway Marker 101.45'  
(4)S.E. Runway Marker 97.20'

APPROVED LAND CORNER  
P.A. 845 of 1990  
Gladwin County

Co. Rep. John Meyer  
Date 5/18/97

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- Found R/R spike 1.75' South of reference point 1/2" x 18" rored in grass area and 227' East of apron plane parking area. Set Gladwin County Re-mon in place of found R/R spike.

See dossier for detailed report.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-3: Corner common to Sections 6 & 7.  
Set 5/8" x 36" rored with Gladwin County Re-mon Cap marked P.S.#27458.

Witnesses:  
N70E face of 6" Windsock Pole 237.55'  
N85W 1/2" x 18" rored, SE corner of Apron  
Plane Parking Tarmac 277.53'  
N47W SE corner (leg) Beacon Tower 422.25'  
North 1/2" x 18" rored 1.75'

SURVEY &  
REMONUMENTATION

JAN 08 1998

SECTION

Signed by Mark R. Robison  
Surveyor's Michigan License No. 27458



Date 10-7-97