

GLADWIN COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 170

For corners in

<u>GLADWIN</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 18N R 1W	D-3
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN  
GLADWIN COUNTY  
FILED - Remonumentation

17 OCT 97 1:19 P.M.

BONNIE K. HOUSE  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, MARK R. ROBISON, in a field survey on May 6, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3			●									
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

1877 T. Gale Merrill  
Set Post  
Wit.-(1)N85E 15 links 7" Maple  
(2)South 5 links 9" Maple

1960 Edmands Eng.--Railroad maps  
Set Iron  
Wit.-(3)Pow Pole 161.10' SW  
(4)12" Pine 94.79'SE

1972 Courtwright  
1/2" rod  
Wit.-(5)Fence Post 34.80' S85W  
(6)Fence Post 16.79' S85E  
(7)Pine 94.79' S40E

1979 Lapham survey  
Found 1" iron  
Wit.-(8)East 16.95' Tele Pole  
(9)West 35.10' Corner Post  
(10)S45W 41.90' Fence Post

1980 Lapham L.C.R.C.#236  
Wit.-same as (8),(9)&(10)

1990 Lapham survey  
Found 1/2" iron  
Wit.-(11)SW 32.41' - 8" Ash  
(12)SSW 40.05' - 10" Ash  
(13)WNW 90.36' - 16" Maple

Misc. Lapham Working Drawing  
Wit.-same as (5)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" x 18" rerod over 1" x 36" iron in centerline of county road opposite fences East & West. Found (7); nail in 14" Pine, measured 94.70', recorded 94.79'. Set Gladwin County Re-mon in place of Found 1" iron.

See dossier for detailed report.

APPROVED LAND CORNER  
P.A. 315 of 1990  
Gladwin County

Co. Rep. [Signature]  
Date 9/18/97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-3: Corner common to Sections 5 & 8.  
Set 5/8" x 36" rerod with Gladwin County Re-mon Cap marked P.S.#27458

Witnesses:  
East 5" W. Pine, nail & tag, 41.55'  
N60E 6" W. Pine, nail & tag, 61.75'  
N30W 5" W. Pine, nail & tag, 93.70'  
N30E 8" W. Pine, nail & tag, 95.35'  
S40E 14" W. Pine, nail, 94.70'

SURVEY &  
REMONUMENTATION

JAN 08 1998

SECTION

Signed by [Signature]  
Surveyor's Michigan License No. 27458



Date 10-7-97