

GLADWIN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

LIBER **001** PAGE **162**

For corners in

<u>GLADWIN</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>18N</u> R <u>1W</u>	<u>D-5</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
 GLADWIN COUNTY
 FILED -Remonumentation
 17 OCT 97 1:18 P.M.
 BONNIE K. HOUSE
 REGISTER OF DEEDS
 Register of Deeds Stamp & File Number

I, MARK R. ROBISON, in a field survey on April 18, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:
 1877 T. Gale Merrill
 Set Post
 Wit.-(1)N43W 22 links 20" Cedar
 (2)S88W 29 links 11" Cedar
 1960 Edmands Eng.-Railroad maps
 Set Iron
 Wit.-(4)spike 6" Poplar 80.89' SW
 (5)spike 4" Poplar 58.92' SE
 1907 County Survey Records
 Set 3' x 3" x 3" Cedar Stake
 Wit.-(3)S89W 23 Links 10" Cedar Stump
 1979 Lapham working dwg & survey

1980 Lapham L.C.R.C.#236
 Set 1/2" roerod
 Wit.-(6)South 23.47' Fence Post
 (7)S45E 28.98' Power Pole
 (8)N60W 54.00 6" Poplar

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" x 18" rod in centerline of T-road N-E-W, old fence post and brushed line South. Found (6); measured 23.47' to face, recorded 23.47'. Found (7); measured 29.0' to nail in power pole, recorded 28.98'. Set Gladwin County Re-mon in place of found iron.

See dossier for detailed report.

APPROVED LAND CORNER
 P.A. 345 of 1990
 Gladwin County

Co. Rep. *Mark Robison*
 Date 10/25/97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-5: Corner common to Sections 8 & 17.
 Set 5/8" x 36" roerod with Gladwin County Re-mon Cap marked P.S.#27458

Witnesses:
 N30E 6" Poplar, nail & tag, 91.28'
 N50W 6" Maple, nail & tag, 64.35'
 S18W 4" Oak, nail & tag, 75.10'
 S15W 6" Poplar, nail & tag, 43.75'

**SURVEY &
 REMONUMENTATION**

JAN 08 1998

SECTION

Signed by *Mark Robison*
 Surveyor's Michigan License No. 27458

Date 10-7-97

