

GLADWIN COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBEX 001 PAGE 163

For corners in

<u>GLADWIN</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>18N</u> R <u>1W</u>	<u>E-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
GLADWIN COUNTY
FILED - Remonumentation

17 OCT 97 1:18 P.M.

BONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, MARK R. ROBISON, in a field survey on April 18, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|--|---|
| 1877 T. Gale Merrill
Set Post
Wit-(1)S44E 25 links 24" Pine
(2)S44W 13 links 8" Cedar | 1974 Radcliffe survey
Found 1/2" iron
Wit-(6)8" Poplar S45E 35.20'
(7)10" Poplar N45E 92.64'
(8)10" Poplar S45W 49.95' |
| 1907 County Survey Records
Set 3' x 3" x 3" Cedar Stake
Wit-(3)South 37 links 14" Cedar Stump | 1974 Courtright L.C.R.C.#84
Fd 1/2" iron
Wit-(9)7" Poplar 34.84' S50E
(10)North End Culvert 19.45'
(11)5" Elm 119.44 N80W |
| 1960+- Edmands Eng.-worksheet
Set Iron
Wit-(4)6" Poplar, spike, 50.40' SW
(5)12" Elm, spike, 68.08' SSE | |

- 1980 Lapham L.C.R.C.#236
Found 1/2" iron
Wit-(12)S70W 73.50' - 8" Birch
(13)S05E 32.90' - 4" Apple
(14)S50E 35.00' - 10" Poplar
- 1993 Lapham survey & working dwg.
- 1994 Lapham survey & working dwg.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" x 18" rerod 1" below surface in intersection on county T-road E-W-N, opposite metal post & brush line south. Found (4) & (8); measured 50.2' to center 18" Poplar, recorded (4) 50.40' (8)49.95'. Found (6), (14) & (9); measured 35.2' to center 16" poplar, recorded (6) 35.2' (14) 35.0' (9) 34.84. Found (13); measured 32.8' to center of 6" Apple, recorded (13) 32.9'. Set Gladwin County Re-mon in place of found iron.

See dossier for detailed report.

APPROVED LAND CORNER
P.A. 845 of 1990
Gladwin County

Co. Rep. [Signature]
Date 5/25/97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-5: Corner common to Sections 8, 9, 16, & 17.
Set 5/8" x 36" rerod with Gladwin County Re-mon Cap marked P.S.#27458.

- Witnesses:
S05E 6" Apple, nail & tag, 32.86'
N30E 5" Basswood, nail & tag, 69.95'
N30W 5" Maple cluster, nail & tag, 84.48'
N65W 5" Maple, nail & tag, 96.70'

SURVEY & REMONUMENTATION

JAN 08 1998

SECTION

Signed by [Signature]
Surveyor's Michigan License No. 27458



Date 10-7-97