

GLADWIN COUNTY REMONUMENTATION

LIBER 001 PAGE 179

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

GLADWIN

(County)

Located In:

Corner Code #

1. Public Land Survey

T 18N R 1W

G-1

T R

T R

T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

STATE OF MICHIGAN
GLADWIN COUNTY
FILED - Remonumentation

17 OCT 97 1:20 P.M.

BONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, MARK R. ROBISON, in a field survey on May 27, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
 1877 T. Gale Merrill
 Set Post
 Wit.-(1)S40W 40 links 6" Hemlock
 (2)S50E 6 links 6" Cedar
 1973 Lapham L.C.R.C.#68
 Found 1/2" bar with Cedar Post
 Wit.-None
 1973 Lapham working dwg.
 Wit.-(3)N30W 74.05' Power Pole
 (4)N45E 50.90' Fence Post
 (5)S75E 48.60' - 4" Cedar
 1984-96 Lapham surveys
 Wit.-same as (3),(4)&(5)

Lapham field notes
 Found 3/8" bar
 Wit.-(6)N25W 58.64' P.P.
 (7)N30E 99.28' 10" Birch
 (8)N65E 32.62' Cor Post

1996 Lapham L.C.R.C.
 Liber 001, Page 113

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" Pipe in centerline E-W road, 5' East of centerline of road to South extended. Found (3); recorded 74.05', measured 74.05' to head of bent spike. Set Gladwin County Re-mon in place of found 3/4" Pipe.

GLO recorded 125.40, measured 99.05 offset corner.

See dossier for detailed report.

APPROVED LAND CORNER
 P.A. 345 of 1990
 Gladwin County

Co. Rep. [Signature]
 Date 5/18/97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-1: Corner on township line, common to Sections 3 & 4.
 Set 5/8" x 36" rerod with Gladwin County Re-mon Cap marked P.S.#27458.

Witnesses:
 S45E 6" Poplar, nail & tag, 62.86'
 N45W Power Pole, nail & tag (South side), 73.48'
 West 99.05' SE Corner Section 33, T19N, R1W, Gladwin County Re-mon
 S45E capped iron 47.20'
 North, 1/2" x 36" rerod, 33.00'

SURVEY &
 REMONUMENTATION

JAN 08 1998

SECTION

Signed by [Signature]
 Surveyor's Michigan License No. 27458



Date 10-7-97