

JAN 17 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 78

For corners in

<u>GLADWIN</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>18</u> N R <u>1W</u>	<u>G-6</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

STATE OF MICHIGAN
GLADWIN COUNTY
FILED-REMONUMENTATION

26 DEC 95 10:51 A.M.

BONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, PAUL B. LAPHAM, in a field survey on MAY-NOVEMBER, 1995, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

1877 T. GALE MERRILL
POST
WIT.-(1)BEECH 6" N15°E 41 1/2'
(2)HEMLOCK 12" S70°W 03'

1974 PAUL LAPHAM L.C.R.C. #89
WIT.-FOUND 5/8" BAR
(5)N44°W 58.75' POWER POLE
(6)N60°E 95.60' 3" W. PINE

1967 PAUL LAPHAM
WORKING DWGS & WIT.
WIT.-(3)FD 3/4" BAR P.P. N50°W 58.53'
(4)2" PINE N 75°E 94.4'

1994 PAUL LAPHAM
FOUND 5/8" ROD
WIT.-(7)N45°W POWER POLE SPIKE 58.75'
(8)N65°E 12" POPLAR SPIKE 46.50'
(9)WEST CONC. MON. 33.00'
(10)S35°E 10" POPLAR SPIKE 91.27'
WITNESS FOR GLADWIN CO. ROAD COMM.
CONSTRUCTION.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND C.I. IN C OF ASPHALT ROAD, BRUSHED LINE EAST, MATCH WITNESSES (7), (8), (9) & (10).
FOUND #3 REC. 58.53' MEAS. 58.35 FACE
EXCAVATED TO 1.6' FOUND NOTHING NO REACTION



This Corner established in Gladwin County Remonumentation Program.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-6: CORNER COMMON TO SECTIONS 15 & 16
SET 5/8"x36" RE-ROD WITH 3" GLADWIN COUNTY RE-MON CAP IN MON. BOX MARKED P.S. #9433

WITNESSES:
N45°W 58.75' - SPIKE IN POWER POLE
N65°E 46.50' - SPIKE IN 12" POPLAR
WEST 33.00' - CONCRETE MONUMENT
S35°E 91.27' - SPIKE IN 10" POPLAR
NORTH P.K. NAIL 2.0'
EAST P.K. NAIL 2.0'

APPROVED LAND CORNER
P.A. 345 of 1990
Gladwin County

Co. Rep. [Signature]
Date 12/14/95

Signed by [Signature]
Surveyor's Michigan License No. 9433

Date 12.22-95