

**SURVEY &
REMONUMENTATION**

JAN 17 1996

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER **001** PAGE **79**

For corners in

<u>GLADWIN</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T18N R 1W	G-7
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

STATE OF MICHIGAN
GLADWIN COUNTY
FILED-REMONUMENTATION

26 DEC 95 10:52 A.M.

BONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, PAUL B. LAPHAM, in a field survey on MAY-NOVEMBER, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

1877 T. GALE MERRILL
POST
WIT. (1) HEMLOCK 10" S17°E 36
(2) DO 15" N28°EW 99

1967 PAUL LAPHAM
FOUND 5/8" BAR
WIT.-(9) TELE. POLE N.W. 90.5'
(10) 8" BLAZED PINE 72.1' N.E.
(11) 8" BLAZED PINE 59.9' S.E.

1979 DUNTON SURVEY
NO WITNESSES

1950-94 EDMANDS
DWG, WORK SHEETS & WITNESSES
SET IRON
WIT.-(3) GUARD POST N.W. 59.35'
(4) 8" JACK PINE 59.9'

1974 PAUL LAPHAM L.C.R.C. #89
FOUND 5/8" BAR
WIT.-(12) N42°W 173.10' S.E. COR. TWP. HALL
(13) N36°E 8" R. PINE 72.60'
(14) S54°E 60.65' 10" JACK PINE

1994 PAUL LAPHAM WIT. FOR GLADWIN CO.
ROAD CO. ROAD COMM.
FOUND 5/8" BAR
WIT. (15) N42°W S.E. COR. TWP. HALL 173.10'
(16) N36°E 8" RED PINE 72.55'
(17) S54°E 10" J. PINE 60.55'
(18) S40°W 6" J. PINE 65.20'
FOUND 5/8" BAR

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

NO REACTION, SET COR. FROM WIT. # (15), (16), (17) & (18) IN Q ASPHALT ROAD FOUND # (6), REC. 173' 6" MEAS. 173.10'
FOUND # (4) REC 59.9'. MEAS 59.9' FACE FOUND # (8), REC. 60.0' MEAS. 60.0± TO FACE
MEAS. G-7 TO G-8, PAUL LAPHAM 2637.08', EDMANDS 2636.37', RE-MEAS. PAUL LAPHAM 2637.67' EXCAVATED BELOW ASPHALT,
FOUND 2 1/2" PIPE 1' BELOW SURFACE, FIT WIT.

This Corner established in Gladwin County Remonumentation Program.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-7: CORNER COMMON TO SECTIONS 15, 16, 21 & 22
SET 5/8"x36" RE-ROD WITH 3" GLADWIN COUNTY RE-MON CAP IN MON. BOX MARKED P.S. 9433

WITNESSES:
N42°W 173.15' - S.E. COR. TWP. HALL
N36°E 72.55' - SPIKE & TAG IN 8" RED PINE
S54°E 60.55' - SPIKE IN 10" JACK PINE
S40°W 65.20' - SPIKE IN 6" JACK PINE
NORTH P.K. NAIL 2.0'
EAST P.K. NAIL 2.0'

APPROVED LAND CORNER
P.A. 345 of 1990
Gladwin County

Co. Rep. [Signature]
Date 12/14/95

Signed by Paul B. Lapham
Surveyor's Michigan License No. 9433

Date 12-22-95