

**SURVEY & REMONUMENTATION**

JAN 17 1996

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER **001** PAGE **72**

For corners in \_\_\_\_\_

GLADWIN  
(County)

Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey T18N R1W G-9  
T R  
T R  
T R

2. Property Controlling in Section S T R  
S T R  
S T R

3. Miscellaneous Property in Sec. S T R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
GLADWIN COUNTY  
FILED-REMONUMENTATION

26 DEC 95 10:50 A.M.

BONNIE K. HOUSE  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, PAUL B. LAPHAM, in a field survey on MAY-NOVEMBER, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

- A. Description of original monument and accessories and/or subsequent restoration:
- 1877 T. GALE MERRILL POST  
WIT.-(1)PINE 16 S73°W 14  
(2)CEDAR 10 N85°E 26
  - 1950 EDMANDS  
WIT.-(6)POWER POLE N.W. 52.15'  
(7)STOP SIGN N.E. 62.1'  
(8)POST WEST 28.3'
  - 1962 EDMANDS SURVEY #1961  
NO WITNESSES
  - 1979 DUNTON SURVEY  
NO WITNESSES
  - 1950 DUNDAS FOUND RR IRON SET BY KNOX  
WIT.-(3)POWER POLE N.W. 52.2'  
(4)N.E. STOP SIGN 62.3'  
(5)S.W. ROAD SIGN 46.3'

NO DATE PAUL LAPHAM  
WIT.-(9)S50°W 78.22' R.L.S. TAG #11192 8" MAPLE  
(10)N30°W, N&T P.P. 52.58'  
(11)S30°E TAG 8" MAPLE 96.81'

1994 PAUL LAPHAM  
UNRECORDED WITNESSES FOR GLADWIN COUNTY  
ROAD COMM.  
FOUND IRON  
WIT.-(12)S50°W 8" MAPLE 78.12'  
(13)N30°W POWER POLE 52.52'  
(14)S30°E 8" MAPLE 96.76"  
(15)N45°E 8" POPLAR 90.05'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

NO CORNER FOUND, RESET FROM P.B.L. WIT. # (12), (13), (14) & (15), 0.5' WEST OF CENTER LINE IN ASPHALT ROAD FOUND # (9), REC. 78.22', MEAS. 78.09', FOUND # (10) REC. 52.52', MEAS. 52.58' FOUND # (3) & # (6) REC. 52.15' & 52.2', MEAS. 52.2' TO FACE POWER POLE. MEAS. G-9 - H-9 - EDMUNDS 2630.0' DUNTON 2630.02', PAUL LAPHAM 2630.0' EXCAVATED UNDER ASPHALT, FOUND 1/2" IRON 1.5' BELOW SURFACE



This Corner established in Gladwin County Remonumentation Program.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-9: CORNER COMMON TO SECTIONS 21, 22, 27 & 28 SET 5/8" RE-ROD WITH 3" GLADWIN COUNTY RE-MON CAP IN MONUMENT BOX MARKED P.S. #9433

- WITNESSES:
- S50°W 78.12' - NAIL & TAG IN 8" MAPLE
  - N30°W 52.58' - NAIL & TAG IN POWER POLE
  - S30°E 96.76' - SPIKE IN 8" MAPLE
  - N45°E 90.05' - NAIL & TAG IN 8" POPLAR
  - NORTH P.K. NAIL 2.0'
  - EAST P.K. NAIL 2.0'

APPROVED LAND CORNER  
P.A. 345 of 1990  
Gladwin County

Co. Rep. J.H. Meyers  
Date 12/14/95

Signed by Paul B. Lapham  
Surveyor's Michigan License No. 9433

Date 12-22-95