

**SURVEY &
MONUMENTATION**

JAN 17 1996

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>GLADWIN</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 18N R 1W	G-11
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

BOOK **001** PAGE **81**

STATE OF MICHIGAN
GLADWIN COUNTY
FILED-REMONUMENTATION

26 DEC 95 10:52 A.M.

BONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, PAUL B. LAPHAM, in a field survey on MAY-NOVEMBER, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

1877 T. GALE MERRILL
SET POST
WIT.-(1)PINE 16" S73°W 14'
(2)CEDAR 10" N88°E 26'

1977 PAUL LAPHAM, L.C.R.C. #153
FOUND 1/2" IRON
WIT.-(3)N45°W 32.85' S 510°E OF W.
END 36" C.M.P.
(4)N45°E 33.65' TOP CENTER OF
E. END 36" C.M.P.
(5)S45°W 30.3' TOP CENTER OF
E. END 15" C.M.P.

1971 PAUL LAPHAM, SURVEY #1309
NO WITNESSES

1976 PAUL LAPHAM, SURVEY #760908
WIT.- SAME AS (3), (4) & (5)
AND WORKING DWG.

1983 PAUL LAPHAM, SURVEY #834761
WIT.-SAME AS (3), (4) & (5)

1992 PAUL LAPHAM, SURVEY #G-923085
WIT.- SAME AS (3), (4) & (5)

1994 LEDY, SURVEY #1002499
SET COTTON GN SPINDLE
WIT.-(6)N.W. 64.0' TO W. END 36" TOP CULVERT
(7)N.E. 63.5' TO E. END 36" TOP CULVERT
(8)S.E. 72.0' TO CENTERLINE TOP MBT BOX
(9)S.W. 50.00' TO CENTERLINE STOP SIGN POST

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 6"x3/8" GEAR END SPIKE 1" BELOW SURFACE OF ASPHALT AT INTERSECTION OF COUNTY ROAD,
SET MON. IN PLACE OF FOUND CORNER, MEAS. 2645.35' TO N 1/4 COR., SEC. 34, REC. SURVEY #1309 2645.44'.

This Corner established in Gladwin County Remonumentation Program.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-11: CORNER COMMON TO SECTIONS 27, 28, 33 & 34
SET 5/8"x36" RE-ROD WITH GLADWIN COUNTY RE-MON CAP, MARKED P.S. #9433.

WITNESSES:
N35°E 63.8' - E. TOP CENTER 24" C.M.P.
N35°W 64.0' - W. TOP CENTER 24" C.M.P.
S45°E 113.05' - NAIL & TAG IN 8" POPLAR
S45°W 79.14' - 5/8"x36" RE-ROD
NORTH P.K. NAIL 2.0'
EAST P.K. NAIL 2.0'



APPROVED LAND CORNER
P.A. 345 of 1990
Gladwin County

Co. Rep. [Signature]
Date 12/14/95

Signed by Paul B. Lapham
Surveyor's Michigan License No. 9433

Date 12-22-95