

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

GLADWIN

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 18N R 1W H-1
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

STATE OF MICHIGAN
GLADWIN COUNTY
FILED - Remonumentation

17 OCT 97 1:21 P.M.

BONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, MARK R. ROBISON, in a field survey on May 2, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1877 T. Gale Merrill
No Corner set
- 1996 Lapham survey
Found 1/2" iron
Wit.-(3)NW 102.6' tag in Cor Fe Post
(4)South 34.9' tag in Cor Fe Post
(5)South 33.00' - 1/2" iron
- 1972 Courtwright L.C.R.C.#31
Set 5/8" x 18" bar
Wit.-(1)NW Cor Post 102.6'
(2)South Fe Post 33.0'
- 1972 Courtwright survey
- 1973 Lapham survey & working dwg.

APPROVED LAND CORNER
P.A. 345 of 1990
Gladwin County

Co. Rep. [Signature]
Date 9/18/97

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" x 18" rerod in centerline of road 1' below surface opposite fence South. Found (1) and (3) as recorded and measured 102.6'. Found (4); corner post leaning, set upright, measured 35' +/-, recorded 34.9'. Set Gladwin County Re-mon in place of found 1/2" x 18" rerod.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-1: Corner on township line, Section 3.
Set 5/8" x 36" rerod with Gladwin County Re-mon Cap marked P.S.#27458.

- Witnesses:
- S30E 6" Poplar, nail & tag, 72.15'
 - N65W Power Pole, nail & tag, 128.35'
 - North, 1/2" x 36" rerod, 32.55'
 - South, 1/2" x 36" rerod, 33.90'
 - West, S 1/4 Cor., Sec.34, T19N, R1W, Gladwin County Re-mon 28.20'

SURVEY &
REMONUMENTATION

JAN 08 1998

SECTION

Signed by [Signature]
Surveyor's Michigan License No. 27458

Date 10-7-97

