

GLADWIN COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 165

For corners in

<u>GLADWIN</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>18N</u> R <u>1W</u>	<u>H-5</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

STATE OF MICHIGAN  
GLADWIN COUNTY  
FILED - Remonumentation

17 OCT 97 1:18 P.M.

BONNIE K. HOUSE  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, MARK R. ROBISON, in a field survey on April 18, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5								●					
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:  
 1877 T. Gale Merrill Set Post  
 Wit.-(1)S73W 12 links 8" Cedar  
 (2)North 3 1/2 links 24" Pine  
 1960+- Lapham survey Set monument in fence corner  
 Wit.-(3)2" Pine S45W 51.80'  
 (4)Ash N30W 40.5'  
 (5)Birch N85W 60.30'  
 1960 Edmands Eng.-working drawing  
 1988 Lapham survey Found concrete monument  
 Wit.-(6)N35W 8" Maple 20.45'  
 (7)S45W 8" W. Pine 51.80'  
 (8)S10E 8" Poplar 70.55'

APPROVED LAND CORNER  
P.A. 345 of 1990  
Gladwin County

Co. Rep. [Signature]  
Date 9/25/97

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 Found concrete monument in fence corner 50' south of C.P. railroad grade. Found witnesses (3), (6) & (7) as recorded & measured.  
 Accepted concrete monument as corner.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-5: Corner common to Sections 10 & 15.  
 Concrete monument reference with Gladwin County Re-mon Cap marked P.S.#27458 on South side.

Witnesses:  
 N45W 4"-6" cluster of Maples, nail & tag, 51.85'  
 S40W 10" Pine, nail & tag, 51.85'  
 S35E 4" Poplar, nail & tag, 32.80'  
 N10E 8" Maple, nail & tag, 63.60'

SURVEY & REMONUMENTATION

JAN 08 1998

SECTION

Signed by [Signature]  
 Surveyor's Michigan License No. 27458



Date 10-7-97