

GLADWIN COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 181

For corners in

<u>GLADWIN</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 18N R 1W	1 - 1
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
GLADWIN COUNTY
FILED - Remonumentation

17 OCT 97 1:21 P.M.

BONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, MARK R. ROBISON, in a field survey on May 2, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:
1877 T. Gale Merrill
No witnesses
1981 Lapham survey & working dwg.
Found 5/8" iron
1972 Courtwright L.C.R.C.#31
Set 5/8" bar
Wit.-(4)S40W 2" Maple 46.90'
(5)S50E Tele Pole 68.44'
(6)N40W Power Pole 67.00'
1995 Lapham survey & working dwg.
Wit.-same as (4),(5)&(6)

APPROVED LAND CORNER
P.A. 345 of 1990
Gladwin County

Co. Rep. [Signature]
Date 9/18/97

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found 1/2" x 18" bar 6" below surface of centerlines of county T-road to South. Found (1) & (6); recorded 67.1' & 67.0', measured 67.1' to spike. Found (4); recorded 46.9', measured 47' to center of tree. Set Gladwin County Re-mon in place of found 1/2" bar.

GLO recorded 99.00, measured 99.05 offset corner.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-1: Corner on township line, common to Sections 2 & 3.
Set 5/8" x 36" rod with Gladwin County Re-mon Cap marked P.S.#27458.

Witnesses:
N45W Power Pole, nail and tag (M.S.H.D.), 67.50'
N10E SW corner of House, block at ground level, 78.90'
S12W 10" Maple, nail and tag, 108.29'
N70E 14" Maple, nail and tag, 98.62'
West, SW Cor., Sec. 35, T19N, R1W, Gladwin County Re-mon 27458

SURVEY & REMONUMENTATION

JAN 08 1998

SECTION

Signed by [Signature]
Surveyor's Michigan License No. 27458

Date 10-7-97

