

GLADWIN COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 182

For corners in

GLADWIN

(County)

Located In:

Corner Code #

1. Public Land Survey	T 18N R 1W	J - 1
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
GLADWIN COUNTY
FILED -Remonumentation

17 OCT 97 1:21 P.M.

BONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, MARK R. ROBISON, in a field survey on May 2, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:
1877 T. Gale Merrill
No corner set
1995 Lapham survey & working dwg
Found 1/2" iron
Wit.-same as (1),(2)&(3)
1982 Lapham L.C.R.C.#259 and survey and working drawing
Set capped iron
Wit.-(1)S25W 18" Pine 51.75'
(2)S15E 18" Pine 49.56'
(3)N50W 4" Birch 27.43'--set capped iron midway online
1995 Lapham
Set capped iron midway & on line
Wit.-(4)16" R. Pine S15E 73.95'
(5)24" W. Pine, North 56.75'
(6)20" R. Pine N50E 82.10'
(7)24" R. Pine S40W 52.55'

APPROVED LAND CORNER
P.A. 345 of 1990
Gladwin County

Co. Rep. [Signature]
Date 5/18/97

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found capped iron in centerline of improved county road. Found (4),(5),(6) & (7) as recorded and measured. Found (1); recorded 51.75', measured 51.7' to face. Found (2); recorded 49.56', measured 51.1' to face. 1982 & 1995 measured across mile-matched well 5437.36' vs. 5437.68'. Set Gladwin County Re-mon in place of found capped iron.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-1: Corner on township line, Section 2.
Set 5/8" x 36" rerod with Gladwin County Re-mon Cap marked P.S.#27458.

Witnesses:
S20E 16" R. Pine, nail & tag, 73.95'
North 20" W. Pine, nail & tag, 56.75'
N50E 14" R. Pine, nail & tag, 82.10'
S40W 20" R. Pine, nail & tag, 52.55'
West, S 1/4 Cor., Sec. 35, T19N, R1W, Gladwin County Re-mon

SURVEY & REMONUMENTATION

JAN 08 1998

SECTION

Signed by Mark R. Robison
Surveyor's Michigan License No. 27458

Date 10-7-97

