

GLADWIN COUNTY REMONUMENTATION

LIBER 001 PAGE 174

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

GLADWIN

(County)

Located In:

Corner Code #

STATE OF MICHIGAN
GLADWIN COUNTY
FILED -Remonumentation

17 OCT 97 1:20 P.M.

BONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- | | | |
|------------------------------------|--|------------|
| 1. Public Land Survey | T <u>18N</u> R <u>1W</u> | <u>J-3</u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| 2. Property Controlling in Section | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| 3. Miscellaneous Property in Sec. | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, MARK R. ROBISON, in a field survey on May 23, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3			2			1
3										●			
4	7		8		9		10			11			12
5													
6	18		17		16		15			14			13
7													
8	19		20		21		22			23			24
9													
10	30		29		28		27			26			25
11													
12	31		32		33		34			35			36
13													

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|---|--|
| 1877 T. Gale Merrill
Set Post
Wit.-(1)N18E 13 links 10" Cedar
(2)S30E 16 links 8" Cedar | 1993 Lapham survey
Wit.-same as (3),(4)&(5) |
| 1986 Lapham survey
Set capped iron midway and online
between the SE and SW Sec. Corners
Wit.-(3)N80W 1.87' - 10" Ash
(4)S10W 6.70' - 11" Ash
(5)S45E 10.80' - 8" Ash | 1996 Lapham survey
Wit.-same as (3),(4)&(5) |

APPROVED LAND CORNER
P.A. 345 of 1990
Gladwin County

Co. Rep. [Signature]
Date 5/20/97

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found capped iron #9433-brushed line East, West and North. Found (3) & (5) as recorded and measured. Set Gladwin County Re-mon in place of found capped iron.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-3: Corner common to Sections 2 & 11.
Set 5/8" x 36" roerod with Gladwin County Re-mon Cap marked P.S.#27458.

Witnesses:


- N80W 12" Ash, nail & tag, 1.87'
- S45E 8" Ash, nail & tag, 10.80'
- N15E 12" Ash, nail & tag, 15.63'
- S40E 10" Ash, nail & tag, 23.30'
- S30W 6" Ash, nail & tag, 17.97'

SURVEY &
REMONUMENTATION

JAN 08 1998

SECTION

Signed by [Signature]
Surveyor's Michigan License No. 27458



Date 10-7-97