

GLADWIN COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 167

For corners in

<u>GLADWIN</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 18N R 1W	J - 5
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN  
GLADWIN COUNTY  
FILED - Remonumentation

17 OCT 97 1:18 P.M.

BONNIE K. HOUSE  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, MARK R. ROBISON, in a field survey on May 23, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5										●			
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

1877 T. Gale Merrill  
Set Post  
Wit.-(1)N88W 28 links 10" Pine  
(2)S60E 8 links 10" Pine

1978 Lapham survey  
Found 1/2" rod  
Wit.-(6)S10W Corner Post 32.00'  
(7)N45E 6" Maple 77.90'  
(8)N30W 2" Pine 39.40'

1975 Lapham survey & working drawing  
Set 1/2" rerod  
Wit.-(3)S10W 32.0' - Corner Post  
(4)N45E 77.90' - 6" Maple  
(5)N30W 39.40' - 2" Pine

1978 Lapham survey  
Found capped iron  
Wit.-(9)S20W Fe Cor 32.05'  
(10)S30W Fe Post 37.70'  
(11)N20W 3" Pine 37.05'  
(12)South Conc. Mon. 33.0'

Lapham Misc. working drawings

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/8" rerod 6 ft. North of centerline of road opposite 8" x 8' metal stan-pipe. Found (12); recorded and measured 33.00'. Set Gladwin County Re-mon in place of found 3/8" iron.

See dossier for detailed report.

APPROVED LAND CORNER  
P.A. 345 of 1990  
Gladwin County

Co. Rep. John W. Meyer  
Date 9/25/97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-5: Corner common to Sections 11 & 14.  
Set 5/8" x 36" rerod with Gladwin County Re-mon Cap marked P.S.#27458.

Witnesses:  
South, Concrete Monument, 33.00'  
North, Twin 5" Pine, nail & tag, 54.20'  
N35W 10" W. Pine, nail & tag, 45.10'  
N70E 6" Maple, nail & tag, 113.40'

SURVEY &  
REMONUMENTATION

JAN 08 1998

SECTION

Signed by Mark R. Robison  
Surveyor's Michigan License No. 27458



Date 10-7-97