

SURVEY & REMONUMENTATION COMMISSION
 APR 07 1995

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

GLADWIN
(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>18N</u> R <u>1W</u> | <u>K-4</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

STATE OF MICHIGAN
 GLADWIN COUNTY
 RECORDED

28 DEC 94 3:01 P.M.

BONNIE K. HOUSE
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, PAUL B. LAPHAM, in a field survey on NOVEMBER, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1887 T. GALE MERRILL
 SET OR POST
 WIT.-CEDAR 11" N5°W 14
 HEMLOCK 12" S67°E 28

1990 LAPHAM - SURVEY

1992 J. FOKENS L.C.R.C. #342
 FOUND 1/2" W/P.B.L. CAP
 WIT.-N5°E 49.60' NAIL & TAG IN WEST FACE 12" PINE
 N10°E 43.65' NAIL & TAG IN WEST FACE 9" PINE
 SSW 62.96' SPIKE IN 24" OAK
 WSW 98.52' SPIKE IN 36" PINE

1971 LAPHAM, FIELD NOTES & SEC. SUBDIVISION

1982 MUELLER - L.C.R.C. #275
 FOUND SPIKE, SET 1/2"x18" IRON & CAP
 WIT.-NW 35.38' SPIKE IN 10" PINE
 NNE 27.45' SPIKE IN 12" PINE
 SSW 62.96' SPIKE IN 24" OAK
 WSW 98.52' SPIKE IN 30" PINE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2"x18" IRON 4' SOUTH OF C. ROAD, SEARCH FOUND NO OTHER CORNER EVIDENCE
 WSW 98.52' SPIKE IN 30" PINE MEAS. 97.30'
 SSW 62.96' SPIKE IN 24" OAK MEAS. 58.80'
 N5°E 49.60' NAIL & TAG IN WEST FACE 12" PINE MEAS. 49.62'
 N10°W 43.65' NAIL & TAG IN WEST FACE 9" PINE MEAS. 43.70'
 VERIFIED LOCATION FROM LAPHAM SURVEY #G-900236 & FIELD NOTES
 VERIFIED LOCATION FROM POKENS SURVEY 91-10-128
 SET CORNER FROM 1/2 IRON & WITNESSES OF RECORD AND SURVEYS.

APPROVED LAND CORNER
 P.A. 345 of 1990
 Gladwin County

Co. Rep. John M. [Signature]
 Date 12-19-94

Accepted as best available evidence of the position of the original corner & replaced with Standard Monument.

Corner, K-4 was approved for remonumentation at a Peer Review Committee Meeting on 12/19, 19 94.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-4: Corner common to Sections 11 & 12
 SET 5/8" x 36" RE-ROD WITH GLADWIN COUTNY RE-MON CAP, MARKED P.S. #9433.
 WITNESSES:
 N05°E 12" W. PINE - NAIL & TAG - 49.62'
 N10°W 9" W. PINE - NAIL & TAG - 43.70'
 S5°W 24" OAK (SPIKE) - 58.80'
 S80°W 36" W. PINE SPIKE - 97.30'



Signed by Paul B. Lapham Date 12-23-94
 Surveyor's Michigan License No. 9433