

SURVEY & REMONUMENTATION COMMISSION
APR 07 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

GLADWIN
 (County)

Located In:

Corner Code ≠

- | | | |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>18N</u> R <u>1W</u> | <u>K-5</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |

STATE OF MICHIGAN
 GLADWIN COUNTY
 RECORDED

28 DEC 94 2:58 P.M.

BONNIE K. HOUSE
 REGISTER OF DEEDS

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, PAUL B. LAPHAM, in a field survey on NOVEMBER, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1877 T. GALE MERRILL
 SET POST
 WIT.-CEDAR 8" S19°E 11
 B. ASH 16" N27°W 24
- 1976 EDMAND, LOCATION MAP
- 1978 LAPHAM, WORKING DWG.
 FOUND 1/4" IRON
 WIT.-SOUTH 10" MAPLE 68.55'
 S45°E 10" MAPLE 69.20'
 S30°W 10" MAPLE 57.90'

APPROVED LAND CORNER
P.A. 345 of 1990
Gladwin County

Co. Rep. [Signature]
 Date 12-2-94

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/8" IRON 4' NORTH OF CENTER LINE GRAVEL ROAD. SEARCHED-FOUND NO OTHER CORNER EVIDENCE.
 SOUTH 10" MAPLE 68.55, MEAS. 68.33' - (SPIKE)
 S45°E 10" MAPLE 69.20', MEAS. 69.13' - (SPIKE)
 S30°W 10" MAPLE 57.90', MEAS. 58.0' - (SPIKE)
 SET COR. FROM WITNESSES AND FOUND 3/8" IRON

Accepted as best available evidence of the position of the original corner & replaced with Standard Monument.

Corner, K-5 was approved for remonumentation at a Peer Review Committee Meeting on 12/2, 19 94.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-5: Corner common to Sections 11, 12, 13 & 14
 SET 5/8"x36" RE-ROD WITH GLADWIN COUNTY RE-MON CAP, MARKED P.S. #9433.
 SOUTH 10" MAPLE (SPIKE) 68.33'
 S45°E 14" MAPLE (SPIKE) 69.13' - NAIL & TAG
 S30°W 10" MAPLE (SPIKE) 58.00'
 N25°W 10" ELM 52.00' - NAIL & TAG



Signed by [Signature]
 Surveyor's Michigan License No. 9433

Date 12-23-94