

**SURVEY &
REMONUMENTATION
COMMISSION**

APR 07 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

PAGE 57
STATE OF MICHIGAN
GLADWIN COUNTY
RECORDED

For corners in

GLADWIN
(County)

Located In:

Corner Code #

- | | | | | | |
|---------------------------------------|---|-----|---|----|-----|
| 1. Public Land Survey | T | 18N | R | 1W | K-7 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling
in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous
Property in Sec. | S | | T | R | |
| | S | | T | R | |

28 DEC 94 3:01 P.M.

BONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, PAUL B. LAPHAM, in a field survey on NOVEMBER, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|---|---|
| <p>1877 T. GALE MERRILL
SET POST
WIT.-B. ASH 11" NB1°E 09
DO 17" S07°W 21</p> <p>1967 EDMAND, LOCATION MARKER & WORK DRAWINGS
SET IRON
WIT.-SPIKE IN TELE POLE STUD 50.84' N.W.
TOP FACE OF RED & WHITE PIPE MARKER 35.15' S.W.
N.E. CORNER WING WALL N.W. 25.80'
S.E. CORNER WING WALL S.W. 29.30'</p> | <p>1975 DOUGLAS W. HOOTH L.C.R.C. #129
FOUND 3" CEDAR POST SCAPER BLADE
WIT.-S45°E 46.68' COR. FENCE POST
N30°W 106.50' S.E. COR. HOUSE
N55°W 45.79' TELE. POLE
S10°W 51.15' MAIL BOX</p> <p>1980 LAPHAM, FIELD NOTES
WIT.-N50°W 45.35' TELE. POLE
S45°E 47.50' CORNER POST
NORTH 33 1/2" IRON CAPPED
N20°W 58.65' 3" CEDAR</p> |
|---|---|

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/8" RE-ROD INTERSECTION OF GRAVEL ROAD EAST & WEST AND ROAD SOUTH, FOUND GRADER BLADE
6.25' WEST OF 3/8" RE-ROD. SEARCHED-FOUND NO OTHER CORNER EVIDENCE.
N30°W 106.50' S.E. COR. HOUSE, MEAS. 106.20' TO GRADER BLADE
N55°W 45.79' TELE. POLE, MEAS. 45.35' - NAIL & TAG TO GRADER BLADE
N20°W 58.65' 3" CEDAR, MEAS. 58.65' - NAIL & TAG TO GRADER BLADE
MEASURED FOUND 3/8" IRON TO S 1/4 COR. 2723.29' 9/10/94
SPIKE IN TELE. STUD POLE 50.84', MEAS. N60°W 50.84' 9/10/94
EDMAND - WORK DWG. & LOCATION, MEAS. S.W. - S 1/4 2723.34'
LAPHAM - SURVEY, MEAS. S.W. - S 1/4 2723.29' 1979
SET COR. IN FOUND LOCATION OF 3/8" RE-ROD AND WITNESSES

APPROVED LAND CORNER
P.A. 345 of 1990
Gladwin County

Co. Rep. *Paul B. Lapham*
Date 12-2-94

Accepted as best available evidence of the position of the original corner & replaced with Standard Monument.

Corner, K-7 was approved for remonumentation at a Peer Review Committee Meeting on 12/2, 19 94.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-7: Corner common to Sections 13, 14, 23 & 24
SET 5/8" x 36" RE-ROD WITH GLADWIN COUNTY RE-MON CAP, MARKED P.S. #9433.
WITNESSES:
N60°W TELE. STUD POLE - NAIL & TAG - 50.84'
N30°W S.E. CORNER OF HOUSE 109.38'
N20°W 3" CEDAR - NAIL & TAG 60.60'
S10°W MAILBOX LEG - NAIL & TAG - 54.00'



Signed by *Paul B. Lapham* Date 12-23-94
Surveyor's Michigan License No. 9433