

SURVEY & REMONUMENTATION
APR 07 1995
GLADWIN COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in _____
 (County) **GLADWIN**

Located In: _____ Corner Code **#** _____

1. Public Land Survey	T <u>18N</u> R <u>1W</u>	<u>K-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
 GLADWIN COUNTY
 RECORDED

28 DEC 94 2:59 P.M.

BONNIE K. HOUSE
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, PAUL B. LAPHAM, in a field survey on NOVEMBER, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1877 T. GALE MERRILL SET POST WIT.-HEMLOCK 12" S13°E .08 DO 6" N16°E .22
 - 1989 LAPHAM, SURVEY FOUND 1/2" IRON WIT.-S45°W 4" POPLAR 45.92' N45°W POWER POLE 85.45' N70°E 4" PIPE
 - 1982 LAPHAM, SEC. SUBDIVISION
 - 1982 LAPHAM, SURVEY FOUND 1/2" IRON WIT.-N60°E 4" PIPE 37.70' N45°W TELE. POLE STUD POLE 54.38' S45°W PIPE LINE MARKER 40.00'

APPROVED LAND CORNER
 P.A. 345 of 1990
 Gladwin County

Co. Rep. J. L. Meyer
 Date 12-2-94

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- FOUND 1/2" RE-ROD IN INTERSECTION OF COUNTY ROADS, 12" BELOW SURFACE, SEARCHED-FOUND NO CORNER EVIDENCE
 N60°E 4" PIPE 37.70', BENT MEAS. 37.7±
 N45°W POWER POLE 85.45', MEAS. 85.45'
 SET CORNER IN FOUND LOCATION OF 1/2" RE-ROD AND WITNESSES

Accepted as best available evidence of the position of the original corner & replaced with Standard Monument.

Corner, K-9 was approved for remonumentation at a Peer Review Committee Meeting on 12/2, 19 94.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-9: Corner common to Sections 23, 24, 25 & 26:
 SET 5/8" x 36" RE-ROD WITH GLADWIN COUNTY RE-MON CAP. MARKED P.S. #9433.
 WITNESS:
 S65°W POWER POLE - NAIL & TAG - 74.75'
 S30°E POWER POLE - NAIL & TAG - 66.90'
 N38°W POWER POLE - NAIL & TAG - 85.45'
 N50°E 5" ASH - NAIL & TAG - 61.02'



Signed by Paul B. Lapham
 Surveyor's Michigan License No. 9433

Date 12-23-94