

SURVEY & REMONUMENTATION
 For corners **APR 07 1995**
GLADWIN COUNTY COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

	Located In:	Corner Code #
1. Public Land Survey	T <u>18N</u> R <u>1W</u>	<u>K-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
 GLADWIN COUNTY
 RECORDED
 28 DEC 94 2:59 P.M.
 BONNIE K. HOUSE
 REGISTER OF DEEDS
Register of Deeds Stamp & File Number

I, PAUL B. LAPHAM, in a field survey on NOVEMBER, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1877 T. GALE MERRILL
 SET POST
 WIT.-HEMLOCK 16" N11°E 7 LKS.
 B. ASH 10" S66°W 47 LKS.
- 1982 LAPHAM, SEC. SUBDIVISION SEC. 25. T18N, R1W
- 1973 LAPHAM, SEC. SUBDIVISION SEC. 26 T18N, R1W
- 1989 CASE, L.C.R.C. #325
 WIT.-N71°W 5" MAPLE 27.61'
 N22°W 4" ELM 52.60'
 S22°E POWER POLE 167.21'
 S56°W 8" OAK 36.99'
- 1974 LAPHAM, L.C.R.C. #79
 SET 1/2"x18" CAPPED IRON
 WIT.-S36°E 162.14' N.W. CORNER BRICK HOUSE (PORCH)
 S56°W 37.30' 6" TWIN OAK
 N40°W 109.1' POWER POLE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2"x18" CAPPED IRON IN Q COUNTY ROAD-CRUSTED AND BENT.
 SEARCHED-FOUND NO OTHER CORNER EVIDENCE.
 S45°E N.W. COR. BRICK HOUSE 162.14' (PORCH)
 S56°W 6" TWIN OAK 36.99' MEAS. 36.93'
 N71°W 5" MAPLE 27.61' MEAS. 27.56'
 CORNER SET BY LAPHAM. PRORATED GOVERNMENT MEAS.
 DISTANCE CHECK BY 0.20± TO THE NORTH & TO THE SOUTH
 SET CORNER IN FOUND LOCATION OF 1/2" C.I. AND WITNESSES.

APPROVED LAND CORNER
 P.A. 345 of 1990
 Gladwin County

Co. Rep. [Signature]
 Date 12-2-94

Accepted as best available evidence of the position of the original corner & replaced with Standard Monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

K-10: Corner common to Sections 25 & 26
 SET 5/8" x 36" RE-ROD WITH GLADWIN COUNTY RE-MON CAP, MARKED P.S. #9433.
 WITNESSES:
 N45°W POWER POLE 111.67' - NAIL & TAG
 S56°W 10" TWIN OAK 36.93'
 S45°E N.W. COR. BRICK HOUSE 167.27'
 N65°E 1/2"x36" RE-ROD 8" BELOW GROUND 33.78'

Signed by Paul B. Lapham Date 12-23-94
 Surveyor's Michigan License No. 9433