

**SURVEY & REMONUMENTATION COMMISSION**

For corners in APR 07 1995

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

PAGE 46

STATE OF MICHIGAN  
GLADWIN COUNTY  
RECORDED

28 DEC 94 2:59 P.M.

RONNIE K. HOUSE  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	GLADWIN (County)	Located in:	Corner Code #
1. Public Land Survey		T <u>18N</u> R <u>1W</u>	<u>K-11</u>
		T _____ R _____	_____
		T _____ R _____	_____
		T _____ R _____	_____
2. Property Controlling in Section	S _____	T _____ R _____	_____
	S _____	T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____	T _____ R _____	_____
	S _____	T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, PAUL B. LAPHAM, in a field survey on NOVEMBER, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- |  |   |
|--|---|
| 1877 T. GALE MERRILL<br>SET POST<br>WIT.-HEMLOCK 10" N61°W 15<br>DO 12" S62°E 27 | 1980 J. MEYERS, L.C.R.C. #249<br>FOUND 5/8" IRON<br>WIT.-N45°E STEEL POST 35.55'<br>N35°W STOP SIGN 34.30'<br>S45°E STEEL POST 36.00'           |
| 1979-1990 LAPHAM, (5) SURVEYS  | 1982 LAPHAM   |
| 1977 P.B.L. WORKSHEET, SET CORNER BY & ROAD OCCUPATION                           | 1989 CASE, L.C.R.C. #325<br>WIT.-S52°E FENCE BRACE POST 52.69'<br>S29°E FENCE POST 65.32'<br>S53°W FENCE POST 51.17'<br>N44°W POWER POLE 67.72' |

APPROVED LAND CORNER  
P.A. 345 of 1990  
Gladwin County

Co. Rep. [Signature]  
Date 12-2-94

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" RE-ROD AT INTERSECTION OF COUNTY ROAD 0.7' BELOW SURFACE, SEARCHED-FOUND NO OTHER CORNER EVIDENCE  
S52°E FENCE BRACE POST (NAIL) 52.69', MEAS. 52.92'  
S29°E FENCE POST (NAIL) 65.32', MEAS. 65.39'  
SET CORNER IN FOUND LOCATION & FROM RECORDED WITNESSES.  
SEE FILED DOSSIER FOR ADDITIONAL INFORMATION.

Accepted as best available evidence of the position of the original corner & replaced with Standard Monument.

Corner, K-11 was approved for remonumentation at a Peer Review Committee Meeting on 12/2, 19 94.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-11: Corner common to Sections 25, 26, 35 & 36  
SET 5/8" x 36" RE-ROD WITH GLADWIN COUNTY RE-MON CAP, MARKED P.S. #9433.  
WITNESSES:  
N45°E 1/2" x 36" RE-ROD 0.5' BELOW GROUND 52.65'  
S45°E 1/2" x 36" RE-ROD 0.5' BELOW GROUND 59.23'  
N45°W POWER POLE 68.72' - NAIL & TAG  
S45°E COR. FENCE POST 46.87' - NAIL & TAG



Signed by Paul B. Lapham  
Surveyor's Michigan License No. 9433

Date 12-23-94