

SURVEY & REMONUMENTATION

APR 07 1995

For corners in

GLADWIN COUNTY

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

PAGE 42

STATE OF MICHIGAN
 GLADWIN COUNTY
 RECORDED

28 DEC 94 2:59 P.M.

BONNIE K. HOUSE
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	Located In:	Corner Code #
1. Public Land Survey	T <u>18N</u> R <u>1W</u>	<u>K-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, PAUL B. LAPHAM, in a field survey on NOVEMBER, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- | | |
|--|--|
| 1877 T. GALE MERRILL
SET OR SECTION POST
WIT.-MAPLE 8" N76°W 15'
HEMLOCK 9" S27° 05' | 1988 CASE (P.S. 30079), L.C.R.C. #325
FOUND COR. OR RECORD
WIT.-S81°E COR. FENCE POST 35.08'
N43°E FENCE POST 63.63'
N22°W POWER POLE 85.80'
S67°W 5" POPLAR 64.26' |
| 1982 LAPHAM, SURVEYS SEC. 35
FOUND 1/2" IRON
WIT.-EAST FENCE CORNER 31.02'
N40°W POWER POLE 88.00'
S30°W CABLE MARKER 46.85' | |

APPROVED LAND CORNER
P.A. 345 of 1990
Gladwin County

Co. Rep. [Signature]
 Date 12-2-94

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	15	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 FOUND 1/2" RE-ROD SURROUNDED BY 3 METAL BARS 3/4"x3"x8".
 3/4"x3"x8", 3/4"x3"x18", HEAVILY CRUSTED, 6" TO 30" BELOW SURFACE OF ROAD, 3' WEST CENTERLINE 5' NORTH OF FENCE TO SEARCH- FOUND NO OTHER CORNER EVIDENCE.
 EAST, OPPOSITE FENCE (DOWN) TO WEST
 S81°E CORNER POST 35.08' - MEAS. 35.35'
 S30°W CABLE MARKER 46.85' - MEAS. 45.85'
 N43°E FENCE POST 63.63' - MEAS. 63.63'
 SET CORNER IN FOUND 1/2" RE-ROD POSITION & WITNESSES

Accepted as best available evidence of the position of the original corner & replaced with Standard Monument.

Corner, K-12 was approved for remonumentation at a Peer Review Committee Meeting on 12/2, 19 94.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-12: Corner common to Sections 35 & 36
 SET 5/8" x 36" RE-ROD WITH GLADWIN COUNTY RE-MON CAP, MARKED P.S. #9433.
 WITNESSES:
 N40°E 12" W. PINE - NAIL & TAG - 96.00'
 S20°W POWER POLE - NAIL & TAG - 167.20'
 S80°E FENCE CORNER 35.35'
 N80°W 1/2"x36" RE-ROD 6" BELOW GROUND
 @ OF TRAIL TO WEST



Signed by Paul B. Lapham Date 12-23-94
 Surveyor's Michigan License No. 9433