

SURVEY & REMONUMENTATION COMMISSION
 APR 07 1995
 For corners in GLADWIN (County)

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

PAGE 43

STATE OF MICHIGAN
 GLADWIN COUNTY
 RECORDED

28 DEC 94 2:59 P.M.

BONNIE K. HOUSE
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	Located In:	Corner Code #
1. Public Land Survey	T <u>18</u> R <u>1W</u>	<u>K-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, PAUL B. LAPHAM, in a field survey on NOVEMBER, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1877 T. GALE MERRILL SET POST
WIT.- HEMLOCK 16" N55°W 34 LKS.
MAPLE 10" N79 1/2°E 24 LKS.
 - 1984 MEYERS, L.C.R.C. #288,
FOUND 3/4" IRON
 - 1985 CASE, L.C.R.C. #325,
FOUND CORNER OF RECORD
 - PRIOR TO 1958 DUNDAS FIELD BOOK
FOUND WOOD STAKE, SET 1/2" ROD
WIT.-LARGE CONC. POST NW 40.2
CORNER POST NE 40.1
STOP SIGN SE 26.2
 - 1974 LAPHAM, L.C.R.C. #77
FOUND 3/4" IRON

APPROVED LAND CORNER
P.A. 345 of 1990
Gladwin County

Co. Rep. John Meyers
Date 12-2-94

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- FOUND 5/8" IRON HEAVILY CRUSTED WITH AGE 1' BELOW SURFACE OF INTERSECTION OF GRAVEL COUNTY ROADS, WITH POINTED CEDAR ST (SEARCH, NO OTHER COR. EVIDENCE FOUND)
 FOUND N.W. LARGE CONCRETE POST 40.0' - MEAS. 40.20' - DUNDAS
 FOUND N45°W COR. CONCRETE POST 40.20' - MEAS. 40.27', L.C.R.C. #288 & 77
 FOUND S37°E 8" POPLAR 65.00' - MEAS. 65.03', L.C.R.C. #288
 FOUND N45°W BOLT CENTER 2: SQUARE CONCRETE PILLAR, 41.98' - MEAS. 41.27'
 SET CORNER AND FOUND LOCATION OF 5/8" ROD AND FROM WITNESSES OF RECORD.
 K-13 USED AS CLOSING CORNER FOR T17N, R1W (K-1)


Accepted as best available evidence of the position of the original corner & replaced with Standard Monument.

Corner, K-13 was approved for remonumentation at a Peer Review Committee Meeting on 12/2, 1994.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-13: Corner common to Sections 35 & 36
 SET 5/8" x 36" RE-ROD WITH GLADWIN COUNTY RE-MON CAP, MARKED P.S. #9433.

WITNESS:
 S50°E 8" J. PINE - NAIL & TAG - 87.73'
 S20°W 12" CLUSTER MAPLES - NAIL & TAG - 96.65'
 N45°W 2"x2"x5" CONCRETE POST WITH CENTER BOLT - 41.27'
 S70°W 6" J. PINE - NAIL & TAG - 91.32'
 S37°E 8" POPLAR (NAIL) 65.03'



Signed by Paul B. Lapham Date 12-23-94
 Surveyor's Michigan License No. 9433