

SURVEY & REMONUMENTATION COMMISSION
 APR 07 1995

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in GLADWIN (County) Located In: _____ Corner Code # _____

1. Public Land Survey	T <u>18N</u> R <u>1W</u>	<u>L-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

STATE OF MICHIGAN
 GLADWIN COUNTY
 RECORDED

28 DEC 94 3:00 P.M.

DONNIE K. HOUSE
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, PAUL B. LAPHAM, in a field survey on NOVEMBER, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

1877 T. GALE MERRILL SET POST WIT.-BEECH 15" S16W 112 HEMLOCK 11" N81°E 08	1982 L.C.R.C. #127 SET 1/2"x18" CAPPED IRON WIT.-NW 17.76' (SPIKE) 12" PINE S'LY 11.04' (SPIKE) 30" MAPLE WSW 24.20' (SPIKE) 10" MAPLE E'LY 17.56' (SPIKE) 7" PINE
1961 LAPHAM, SURVEY	
1980 LAPHAM, WORKING DWG.	

APPROVED LAND CORNER
 P.A. 345 of 1990
 Gladwin County

Co. Rep. [Signature]
 Date 12-19-94

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND CAPPED IRON IN FENCE CORNER INTERSECTION, SEARCHED-FOUND NO OTHER CORNER EVIDENCE.
 N.W. 17.76' 12" PINE - MEAS. 17.70'
 S'LY 11.04' 30" MAPLE - MEAS. 11.00'
 N.S.W. 24.20' 10" MAPLE - MEAS. 24.25'
 E'LY 17.56' 7" PINE - MEAS. 17.48'
 SET CORNER IN FOUND LOCATION & WITNESSES

Accepted as best available evidence of the position of the original corner & replaced with Standard Monument.

Corner, L-3 was approved for remonumentation at a Peer Review Committee Meeting on 12/19, 19 94.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-3: Corner common to Sections 1 & 12
 SET 5/8" x 36" RE-ROD WITH GLADWIN COUNTY RE-MON CAP, MARKED P.S. #9433.
 WITNESSES:
 N15°W 12" PINE (SPIKE) 17.70'
 SOUTH 30" MAPLE (SPIKE) 11.00'
 S80°W 10" MAPLE (SPIKE) 24.25'
 N85°E 7" PINE (SPIKE) 17.48'



Signed by Paul B. Lapham Date 12-23-94

Surveyor's Michigan License No. 9433