

**SURVEY & REMONUMENTATION**  
**APR 07 1995**  
**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

GLADWIN  
(County)

Located In:

Corner Code #

- |                                    |         |                          |            |
|------------------------------------|---------|--------------------------|------------|
| 1. Public Land Survey              |         | T <u>18N</u> R <u>1W</u> | <u>L-5</u> |
|                                    |         | T _____ R _____          | _____      |
|                                    |         | T _____ R _____          | _____      |
|                                    |         | T _____ R _____          | _____      |
| 2. Property Controlling in Section | S _____ | T _____ R _____          | _____      |
|                                    | S _____ | T _____ R _____          | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ | T _____ R _____          | _____      |
|                                    | S _____ | T _____ R _____          | _____      |
4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
 GLADWIN COUNTY  
 RECORDED

28 DEC 94 3:00 P.M.

BONNIE K. HOUSE  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, PAUL B. LAPHAM, in a field survey on NOVEMBER, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- 1877 T. GALE MERRILL SET POST
- 1982 LAPHAM, SURVEY
- WIT.-BEECH 15" S16°W 112'
- HEMLOCK 11" N81°E 98'
- 1970 WADE TRIM, WORKSHEET
- 1978 LAPHAM, SURVEY
- WIT.-S45°W 10" POPLAR 69.35'
- S30°W CLUMP MAPLES 54.40'
- NORTH FENCE POST 33.05'
- SOUTH IRON 33.00'

APPROVED LAND CORNER  
 P.A. 345 of 1990  
 Gladwin County

Co. Rep. [Signature]  
 Date 12-19-94

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2"x18" IRON, BENT, 4' SOUTH @ OF GRAVEL ROAD. SEARCHED-FOUND NO OTHER CORNER EVIDENCE.  
 S45°W 10" POPLAR (SPIKE) 69.35' - MEAS. 69.22'  
 S30°W CLUMP MAPLES (SPIKE) 54.40' - MEAS. 54.31'  
 SOUTH 1/2" CAPPED IRON 33.00' - MEAS. 32.94'  
 SET CORNER IN FOUND LOCATION OF 1/2" IRON & WITNESSES.

Accepted as best available evidence of the position of the original corner & replaced with Standard Monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-5: Corner common to Sections 12 & 13  
 SET 5/8" x 36" RE-ROD WITH GLADWIN COUNTY RE-MON CAP, MARKED P.S. #9433.  
 S45°W 14" POPLAR (SPIKE) 69.22'  
 S30°W CLUMP MAPLES (SPIKE) 54.31'  
 N10°W TWIN 12" MAPLES - NAIL & TAG - 70.95'  
 N42°E 8" POPLAR - NAIL & TAG - 68.62'



Signed by Paul B. Lapham Date 12-23-94  
 Surveyor's Michigan License No. 9433