

SURVEY & REMONUMENTATION
APR 07 1995
COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>GLADWIN</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>18N</u> R <u>1W</u>	<u>L-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
 GLADWIN COUNTY
 RECORDED
 28 DEC 94 3:00 P.M.
 BONNIE K. HOUSE
 REGISTER OF DEEDS
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, PAUL B. LAPHAM, in a field survey on NOVEMBER, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1877 T. GALE MERRILL 1979-1988 LAPHAM, SURVEYS
 W. PINE 26 FOR QR SECTION POST
 - 1907 JOHN KNOX, C.S.R.
 - 1979 L.C.R.C. #249
 FOUND 1/4" IRON
 WIT.-S40°W 6" BASSWOOD 51.45'
 N50°E TELE. POLE 49.70'
 N55°W POWER POLE 31.43'
 - WADE, TRIM, EDMAND, WORKSHEET

APPROVED LAND CORNER
 P.A. 345 of 1990
 Gladwin County
 Co. Rep. [Signature]
 Date 12-19-94

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- FOUND 3/8"x18" IRON IN CENTER-LINE ROAD, 0.8' BELOW SURFACE. SEARCHED-NO OTHER CORNER EVIDENCE FOUND.
 FIELD FENCE LINE SOUTH, 4± EAST OF CORNER.
 S40°W 6" BASSWOOD 51.45' - MEAS. 51.39'
 N30°E POWER POLE 31.43' - MEAS. 31.37'
 SET CORNER IN FOUND 1/4" IRON POSITION & WITNESSES

Accepted as best available evidence of the position of the original corner & replaced with Standard Monument.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-7: Corner common to Sections 13 & 24
 SET 5/8" x 36" RE-ROD WITH GLADWIN COUNTY RE-MON CAP, MARKED P.S. #9433.
 S40°W 8" BASSWOOD - NAIL & TAG - 51.39'
 N30°E POWER POLE - NAIL & TAG - 31.37'
 S60°W POWER POLE - NAIL & TAG - 82.00'
 S05°E 12" CORNER POST - NAIL & TAG - 63.65'
 N20°E 6" W. PINE - NAIL & TAG - 111.40'



Signed by [Signature]
 Surveyor's Michigan License No. 9433

Date 12-23-94