

RECORDED  
 FEB 18 1994  
 COMMISSION

Gladwin County Remonumentation

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Gladwin</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>18N</u> R <u>1W</u>	<u>M-10</u>
	T <u>18N</u> R <u>1W</u>	<u>M-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		



Register of Deeds Stamp & File Number

I, Craig W. McVean, in a field survey on October 26, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

**M-10** Set post - J. Brink, 1837.  
 Hemlock 10" S 21-1/2" W 43 Lks.  
 Hemlock 8" N 27° W 26 Lks.

**M-11** Found post - J. Brink, 1837.  
 Hemlock 11" N 26° W 27 Lks.  
 B. Ash 12" S 49° W 39 Lks.

GLO Resurvey - 1877, Merrill.  
 M.D.O.T. witness card - 1981, Gilbert - 3/4" rod in mon. box.  
 M.D.O.T. right-of-way map file #26-R-2, Control Sec. 26031 - Sheet 30.  
 Dundas - Iron pipe and witnesses - prior to 1958.

GLO Resurvey - 1877, Merrill.  
 M.D.O.T. witness card - 1981 - Gilbert - 3/4" iron rod in mon. box.  
 M.D.O.T. right-of-way map - file #26-R-2, Control Section 26031, Sheet 30.  
 Dundas witnesses - prior to 1958.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

**M-10** Standard 1/4 corner common to Sec. 25, T18N, R1W.  
 Found boat spike in mon. box at occupation fence to W - position agrees with M.D.O.T. distance call to E-12-T18N-R1E. Monument accepted as the best available evidence of the position of the original corner. Accepted by Gladwin County Peer Review Group on 12-10-93.

**M-11** Standard Sec. corner common to Sec. 25&36, T18N, R1W.  
 Found 3/4" iron rod in mon. box per M.D.O.T. witness card in agreement with M.D.O.T. and GLO distance call to E-13-T18N-R1E. Monument accepted as the best available evidence of the position of the original corner. Accepted by Gladwin County Peer Review Group on 12-10-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**M-10** Replace boat spike with 2" Gladwin County alum. cap on 5/8" x 24" rebar in mon. box - 0.4'± W of centerline of M-30.  
 S 43° E 47.22' to nail and tag in SW side Fence Post.  
 N 53° E 42.65' to nail and tag in NW side Fence Post.  
 N 26° W 122.57' to nail and tag in SW side P.P.  
 S 85° W 69.64' to nail and tag in N side 8" Pine.  
 S 20° W 118.69' to nail and tag in NW side 10" Maple.  
 S 308.36' (308.35' M.D.O.T.) and 1.38' W to closing corner E-12-T18N-R1E.

**M-11** Could not remove 3/4" iron rod - drove down - set 2" Gladwin County alum. cap on 5/8" x 36" rebar over rod in mon. box 1.6'± E of the centerline of M-30.  
 N 60° W 72.67' to nail and tag in NE side 10" Pine.  
 S 60° W 70.39' to nail and tag in N side P.P.  
 N 85° E 76.45' to nail and tag in N side 8" Ash.  
 N 25° W 82.74' to nail and tag in W side 6" Pine.  
 S 310.69' (310.60' M.D.O.T. and 310.21' GLO) to closing township corner E-13-T18N-R1E.



Signed by Craig W. McVean Date 12/20/93  
 Surveyor's Michigan License No. 39088