

AUG 23 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Gladwin County Remonumentation

001 PAGE 319

For Corners in

GLADWIN

(County)

Located In:

Corner Code#:

- 1. Public Land Survey T. 18N R. 2W A-2
2. Public Controlling in Section S. T. R.
3. Miscellaneous Property in Section S. T. R.
4. Lot No., Recorded Plat
5. Private Claims

STATE OF MICHIGAN
GLADWIN COUNTY
FILED-REMONUMENTATION

10 AUG 2000 11:22:32 AM

BONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on March 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. Cell (2,6) contains a star symbol.

A. Description of original monument and accessories and/or subsequent restoration:

1838 Nicholson-Set QR. Section Post
Wit-(1)Hemlock 6 S42W 15
(2)Do 8 N38W 14

1972 Courtwright
LCRC#42-72
Found 5/8" Rod
Wit-(4)P.P. S80°W 31.56'
(5)Cor Post N85°E 31.97'
(6)P.P. S45°E 47.43'

1984 Lapham--LCRC#286
Found 5/8" Iron
Wit-(7)S85°W Power Pole 32.12
(8)N45°W Fe. Post 41.90
(9)N20°E Power pole 81.30

1903 A. Johnson
Wit-(3)Pine Stump 20 N88 1/2W 53

1981 Lapham--working dwg
Found 5/8" Iron
Wit-none

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found 5/8" x 18" rered, bent on top, 4 feet East of centerline North-South road opposite old vintage fence and corner post (down) to West. Agrees with witnesses (4)Recorded 31.56', measured to face P.P. 31.5' & (9)Recorded & measured 81.30'. Agrees with measurements Lapham (1972) 2654.94' and (1987) 2655.3', Courtwright (1972) 2654.08' and A. Johnson (1903) 2651.55' to A-1. Accepted found 5/8" rod as corner of record; replaced with 5/8" x 36' rered.

APPROVED LAND CORNER
P.A. 345 of 1990
Gladwin County

See dossier for detailed report on corner A-2.

Co. Rep. [Signature]
Date 8-2-00

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" rered with Gladwin Remonumentation cap marked P.S. 27458. Accepted as best available evidence to perpetuate position of corner A-3.

Witnesses:
S85°W Power Pole, nail & tag, 32.00' (OBT)
N20°E Power Pole, spike, 81.30' (OBT)
S30°W 10" W. Pine, nail & tag, 108.50'
N78°E 16" Ash, nail & tag, 164.00'



Signed by [Signature]
Surveyor's Michigan License No. 27458

Date 8-9-00