

AUG 23 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Gladwin County Remonumentation

LIBER 001 PAGE 316

For Corners in
GLADWIN

(County)

Located In:

Corner Code#:

- 1. Public Land Survey T. 18N R. 2W A-7
2. Public Controlling in Section S. T. R.
3. Miscellaneous Property in Section S. T. R.
4. Lot No., Recorded Plat
5. Private Claims

STATE OF MICHIGAN
GLADWIN COUNTY
FILED-REMONUMENTATION

10 AUG 2000 11:21:57 AM

BONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on March 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

Grid table with columns A-M and rows 1-13. Row 2: 6, 5, 4, 3, 2, 1. Row 4: 7, 8, 9, 10, 11, 12. Row 6: 18, 17, 16, 15, 14, 13. Row 8: 19, 20, 21, 22, 23, 24. Row 10: 30, 29, 28, 27, 26, 25. Row 12: 31, 32, 33, 34, 35, 36.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1838 Nicholson
Set Post Cor Sections 13 & 14
Wit-(1)Beech 6 S41 W 25
(2)Synn 9 N65W 44

1977+/- Sedgman
working dwg
Set 1/2" Bar
Wit-(3)S65W 50.13 4" Elm
(4)East 21.42 corner fence post
(5)N55W 59.73 fence post
(6)N30E 49.67 4" Elm

1995 Lapham--LCRC#100-95
Set Clare County Remon
Wit-(7)East 21.42' Cor Fence Post
(8)N52°W, nail & tag, 3d Fence Post
(9)N30°E 49.67' nail & tag, 12" Elm clump of 3
(10)S39°E 42.52' nail & tag, 14" Elm

1972 Lapham--survey & notes
Wit-none

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found Clare County Remon in centerline of road opposite fence to East; agrees with LCRC#100-95. Accepted found Clare County Remon recorded in Clare County Records LCRC#100-95.

See dossier for detailed report on corner A-7.

APPROVED LAND CORNER

P.A. 345 of 1990
Gladwin County

Co. Rep. [Signature]
Date 8-2-00

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found 5/8" x 36" rerod with 3" Clare County Monument cap marked P.S. 27458. Accepted as best available evidence to perpetuate position of corner A-7.

Witnesses:

- N30°E 49.67', nail & tag, 12" Elm, clump of 3 (OBT)
S39°E 42.52', nail & tag, 14" Elm (OBT)
N80°W 16" Ash, nail & tag, 122.80' (NBT)
S45°W Corner Post, nail & tag, 39.60' (NBT)
East 8" Ash, nail & tag, 31.15'



Signed by [Signature]
Surveyor's Michigan License No. 27458

Date 8-9-00