

AUG 23 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Gladwin County Remonumentation

LIBER 001 PAGE 315

For Corners in
GLADWIN

Table with 3 columns: (County), Located In:, Corner Code#:
1. Public Land Survey T. 18N R. 2W A-8
2. Public Controlling in Section S. T. R.
3. Miscellaneous Property in Section S. T. R.
4. Lot No., Recorded Plat
5. Private Claims

STATE OF MICHIGAN
GLADWIN COUNTY
FILED-REMONUMENTATION

10 AUG 2000 11:21:46 AM

BONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on March 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

Grid table with columns A-KLM and rows 1-13. Contains numbers 1-36 in a grid pattern.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1838 Nicholson--Set QR. Section Post
Wit-(1)Sugar 8 S25W 21
(2)Do 8 N52W 8

1972 Lapham--LCRC334,
survey & working dwgs
Set 1/2" Bar
Wit-(5)S75°E 34.95' - 36" Pine Stump
(6)S20°W 98.9' - 15" C.M.P.
(7)East 33.00' - Cor. Post

1977 Sedman-survey
Found 1/2" Bar
Wit-(8)S70°E 21.19 12" Quad. Hickory
(9)S20°E 45.26 6" Elm
(10)S70°W 30.25 Fence Post
(11)N35°W 46.60 Fence Post

1909 Johnson--C.S.R.
Wit-(3)Fe. Post 8 S72W 31
(4)Pine Stump 24 East 67

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found 1/2" x 18" roerod 3 feet East of centerline road opposite old fence to East. Agrees with witnesses (6), (8) & (9). Accepted found 1/2" roerod as corner of record; replaced with 5/8" x 36" roerod.

See dossier for detailed report on corner A-8.

APPROVED LAND CORNER
P.A. 345 of 1990
Gladwin County
Co. Rep. [Signature]
Date 8-9-00

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" roerod with Gladwin Remonumentation cap marked P.S. 27458. Accepted as best available evidence to perpetuate position of corner A-8.

Witnesses:
East 8" Elm, nail & tag, 43.68'
S18°E 12" Ash, nail & tag, 152.30'
N50°E 6" Ash, nail & tag, 45.80'
S12°W Top Center 14" C.M.P. 98.65' (OBT)



Signed by [Signature]
Surveyor's Michigan License No. 27458

Date 8-9-00