

AUG 23 2000

SECTION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Gladwin County Remonumentation

LIBER 001 PAGE 314

For Corners in
GLADWIN

(County)

Located In:

Corner Code#:

- 1. Public Land Survey T. 18N R. 2W A-9
2. Public Controlling in Section S. T. R.
3. Miscellaneous Property in Section S. T. R.
4. Lot No. Recorded Plat
5. Private Claims

STATE OF MICHIGAN
GLADWIN COUNTY
FILED-REMONUMENTATION

10 AUG 2000 11:21:28 AM

BONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on March 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1883 Nicholson--Set Post Sec's 24&25
Wit-(1)Hemlock 11 S45W 25
(2)Do 6 N38W 13

1968 Lapham
Fd Plow Point, Set 5/8" Bar
Wit:none

1908 Johnson--C.S.R.
Wit-(3)W. Pine 36 N54W 83 (54.78)

1972 Lapham--LCRC#34,
survey & working dwgs
Set 1/2" Bar
Wit-(4)N40°E 37.5' - Cor. Post
(5)N45°E 46.2' - Lot Iron
(6)West 32.7' - Cor. Post

1977 Sedgman
Fd 5/8" Bar & Plow Point
Wit:none

APPROVED LAND CORNER
P.A. 345 of 1990
Gladwin County

Co. Rep. [Signature]
Date 8-12-00

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found 5/8" Bar and Plow Point in nest of stones 24" below surface in centerline of road to East and opposite fence to West, opposite old vintage fence to South, where woods start approximately 400 feet+/- South of corner. Does not agree with corner set by Lapham 1972; LCRC#34 said corner location lies 18 feet +/- East. Accepted found 5/8" Iron and Plow Point as corner of record. Did not remove plow point.

See dossier for detailed report on corner A-9.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" rered with Gladwin Remonumentation cap marked P.S. 27458. Accepted as best available evidence to perpetuate position of corner A-9.

- Witnesses:
West 16" Elm, nail & tag, 56.45'
S45°E 8" W. Pine, nail & tag, 49.25'
N62°E 6" Maple, nail & tag, 92.40'
S18°W 14" Elm, nail & tag, 196.15'

Signed by [Signature]
Surveyor's Michigan License No. 27458

Date 8-9-00

