

SURVEY &
REMONUMENTATION

JAN 17 1996

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 69

For corners in **COMMISSION**

GLADWIN (County)	Located In:	Corner Code #
1. Public Land Survey	T18N R2W	A-11
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

STATE OF MICHIGAN
GLADWIN COUNTY
FILED-REMONUMENTATION

26 DEC 95 10:50 A.M.

BONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, PAUL B. LAPHAM, in a field survey on MAY-NOVEMBER, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1856 GEO H. CANNON
SET POST
WIT.-(1)LYNN 15" S88°W 42
(2)ELM 10" N54°W 44

1971 LAPHAM L.C.R.C. #71
FOUND 3/4" IRON STAKE
WIT.-(5)S45°W 44.60' 4" BALSAM
(6)S05°W 33.20' 5" PINE
(7)N45°E 66.95' POWER POLE

1900 COUNTY SURVEY RECORDS
SET POST 1x3x3
BEER BOTTLE IN NEST OF STONES.
WIT.-(3)PINE STUMP 36" N55 3/4°E 50 LKS
(4)DO 36" S20°W 62 LKS

1991 LAPHAM UNRECORDED L.C.R.C. FOR
COUNTY ROAD CONSTRUCTION
FOUND 3/4" BAR
WIT.-(8)SOUTH 10" W. SPRUCE 33.30'
(9)S45°W 10" SPRUCE 44.35'
(10)N60°E 30" OAK 74.10'
(11)N45°E P.P. 66.85'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" PIPE IN CENTER-LINE GRAVEL ROAD FENCE NORTH & SOUTH, EXCAVATED FOUND NO OTHER CORNER, MATCH'S WITNESS (5) THRU (11), REPLACED WITH GLADWIN RE-MON.



This Corner established in Gladwin County Remonumentation Program.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-11: WEST SECTION CORNER 30-31
SET 5/8"x36" RE-ROD WITH GLADWIN COUNTY RE-MON CAP, MARKED P.S. #9433.

WITNESSES:
SOUTH 33.30' - NAIL & TAG IN 10" WHITE PINE
S45°W 44.30' - NAIL & TAG IN 10" SPRUCE
N60°E 74.08' - NAIL & TAG IN 30" OAK
N45°E 66.90' - NAIL & TAG IN POWER POLE

APPROVED LAND CORNER
P.A. 345 of 1990
Gladwin County

Co. Rep. J. H. Meyer
Date 12/14/95

Signed by Paul B. Lapham
Surveyor's Michigan License No. 9433

Date 12.22.95