

**SURVEY &
REMONUMENTATION**

JAN 17 1996

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

LIBER 001 PAGE 71

For corners in

COMMISSION

STATE OF MICHIGAN
GLADWIN COUNTY
FILED-REMONUMENTATION

26 DEC 95 10:50 A.M.

BONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

<u>GLADWIN</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>18N</u> R <u>2W</u>	<u>C-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, PAUL B. LAPHAM, in a field survey on MAY-NOVEMBER, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

- A. Description of original monument and accessories and/or subsequent restoration:
- 1856 GEO H. CANNON FOUND OLD CORNER
WIT.-(1)HEMLOCK 16" N46°E 20
(2)HEMLOCK 8" S59°W 24
 - 1900 COUNTY SURVEY RECORD CEDAR POST, STONE & IRON (SET)
WIT.-(3)PINE STUMP 30" N17°E 10 LKS
(4)PINE STUMP 26" S19°E 64 LKS
 - 1971 LAPHAM L.C.R.C. #71 & WORKING DWG. FOUND IRON PIPE
WIT.-(5)S45°W 44.60' 4" BALSAM
(6)S05°W 33.20' 5" PINE
(7)N45°E 66.95' POWER POLE
WORKING DWG
(8)POWER POLE S45°W 61.90'
(9)14" OAK N80°E 28.15'
 - 1980 LAPHAM SURVEY #803004 FOUND P.K. NAIL
WIT.-(10)EAST 18" OAK 29.20'
(11)S45°W POWER POLE 61.45'
(12)S33°W COR. POST 52.40'

1985 LAPHAM SURVEY #G-855552 FOUND P.K. REACTIONS UNDER ASPHALT
WIT.-(13)N45°W TELE. RISER 57.24' AND (10) & (11)

1991 UNRECORDED L.C.R.C. FOR COUNTY ROAD CONSTRUCTION TO THE WEST NO CORNER FOUND
SET 1/2"x18" CAPPED IRON FROM RECORD OF PAUL LAPHAM & ASSOC.
WIT.-(14)N40°W CENTER TO RISER 60.35'
(15)EAST 20" OAK 29.20'
(16)S45°W P.P. 61.45'
(17)S35°W CORNER POST 52.80'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON IN MON. BOX IN CENTER LINE ASPHALT ROAD. FENCE TO EAST FOUND WITNESSES # (9), (10) AND (15), REC. 29.20', MEAS. 29.20' MEAS. 2638.02, REC. 1970 WORKING DWG 2638.02', TO S 1/4 COR. SEC. 30 LEFT IRON SET GLADWIN RE-MON CAP.



This Corner established in Gladwin County Remonumentation Program.
See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-11: CORNER COMMON TO SECTIONS 27, 28, 33 & 34
SET GLADWIN RE-MON CAP ON EXISTING IRON IN MON. BOX., MARKED P.S. #9433

WITNESSES:
N40°W 60.30' - CENTER TOP BELL RISER
EAST 29.20' - NAIL & TAG IN 20" OAK
S45°W 61.45' - NAIL & TAG IN POWER POLE
N20°W 148.28' - NAIL & TAG IN POWER POLE
NORTH P.K. NAIL 2.0'
EAST P.K. NAIL 2.0'

APPROVED LAND CORNER
P.A. 345 of 1990
Gladwin County

Co. Rep. [Signature]
Date 12/14/95

Signed by Paul B. Lapham
Surveyor's Michigan License No. 9433

Date 12-22-95