

**SURVEY &
REMONUMENTATION**

JAN 17 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER **001** PAGE **68**

For corners in

<u>GLADWIN</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>18N</u> R <u>2W</u>	<u>E-6</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

STATE OF MICHIGAN
GLADWIN COUNTY
FILED-REMONUMENTATION

26 DEC 95 10:49 A.M.

BONNIE K. HOUSE
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, PAUL B. LAPHAM, in a field survey on MAY-NOVEMBER, 19 95 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1856 GEO. CANNON
SET POST
WIT.-(1)TAMARACK S25°W 15'
(2)B. ASH 7" N15°E 18'

1908 COUNTY SURVEY RECORD
MAP NO WITNESSES

1973 SEDGMAN UNRECORDED L.C.R.C.
FOUND 2" PIPE
WIT.(3)N35°E 105.0' 24" PINE
(4)EAST 33.0' CONC. MON.
(5)S55°W 29.15' 8" ELM

1973 LAPHAM SURVEY NO. 2401
FOUND 2" PIPE
WIT.-SAME AS (3), (4) & (5)

1991 LAPHAM UNRECORDED L.C.R.C.
FOR COUNTY ROADS CONSTRUCTION
FOUND 2" IRON
WIT.-(6)EAST CONC. MON. 33.00'
(7)S30°E POWER POLE 63.60'
(8)N30°W 4" W. PINE 71.35'
(9)N45°E 24" W. PINE 67.62'

1994 LAPHAM SURVEY #G-934017
FOUND 2" PIPE
WIT.- SAME AS (3), (4), & (5)

1995 CLAYPOOL L.C.R.C. 356
SET 3/4" PIPE
WIT.-(10)S50°W 45.43' NAIL IN 6" ELM
(11)N15°E 133.60' NAIL IN P.P.
(12)N35°E 105.00' NAIL IN 30" PINE
(13)N45°W 60.09' NAIL IN 15" BASSWOOD
(14)S35°E 131.19' NAIL IN POWER POLE
PLAT OF KERSWELL LAKE NO. 1

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND CAPPED 3/4" PIPE, EXCAVATED NO OTHER CORNERS FOUND, SET GLADWIN RE-MON FROM FOUND 3/4" PIPE AND WITNESSES (10), (11), (12) & (13), FOUND WITNESSES (3) REC. 105.0' MEAS. 105.0', FOUND WITNESS (4) REC. 33.0' MEAS. 33.00'

This Corner established in Gladwin County Remonumentation Program.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-6: CORNER COMMON TO SECTIONS 16 & 17
SET 5/8"x36" RE-ROD WITH GLADWIN COUNTY RE-MON CAP, MARKED P.S. #9433.

WITNESSES:
EAST 33.00' - CONCRETE MONUMENT
N35°E 105.00' - NAIL & TAG IN 24" W. PINE
N45°W 60.09' - NAIL & TAG IN 15" BASSWOOD
S50°W 45.43' - NAIL IN 6" ELM
S35°E 131.19' - NAIL IN POWER POLE

APPROVED LAND CORNER
P.A. 345 of 1990
Gladwin County

Co. Rep. J. Meyer
Date 12/14/95

Signed by Paul B. Lapham
Surveyor's Michigan License No. 9433

Date 12-22-95