

**SURVEY &
REMONUMENTATION**

JAN 17 1996

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

COMMISSION

For corners in

LIBER 001 PAGE 60

<u>GLADWIN</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>18N</u> R <u>2W</u>	<u>G-1</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

STATE OF MICHIGAN
GLADWIN COUNTY
FILED-REMONUMENTATION

26 DEC 95 10:47 A.M.

RONNIE K. HOUSE
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, PAUL B. LAPHAM, in a field survey on MAY-NOVEMBER, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

1856 GEO H. CANNON
SET POST
WIT.-(1)BEECH 11" N26°E 8
(2)HEMLOCK 8" N61°W 11

1976 EDMANDS SURVEY
R.R. SPIKE
WIT.-(3)WEST 29.95' TO 1/2" RE-ROD
(4)N.E. 47.7' NAIL IN P. POLE
(5)N.W. 47.35' TO FACE P.POLE

1984 LAPHAM SURVEY #844962
FOUND R.R. SPIKE
WIT.-SAME AS (3), (4) & (5)

1969 LAPHAM SURVEY #8367
NO WITNESSES

1977 EDMANDS L.C.R.C. #166
SET 1/2" RE-ROD
WIT.-SAME AS (3), (4) & (5)

1986 LAPHAM SURVEY #G-866762
FOUND R.R. SPIKE
WIT.-SAME AS (3), (4) & (5)

1972 COURTRIGHT SURVEY
NO WITNESSES

1980 LAPHAM SURVEY #802849
FOUND ROD
WIT.-SAME AS (3), (4) & (5)

1991 LAPHAM UNRECORDED L.C.R.C.
FOR COUNTY ROAD CONSTRUCTION
FOUND 1/2" RE-ROD
WIT.-(7)S45°E 16" CHERRY 53.65'
(8)SOUTH N&T IN ASPHALT 55.00'
(9)N45°W POWER POLE 47.63'
(10)N.E. POWER POLE 47.55'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

SET P.K. NAIL IN ASPHALT, CENTER LINE ROAD SOUTH FROM WITNESSES (7), (8), (9) & (10) EXCAVATED NO CORNER FOUND.
SET GLADWIN RE-MON, MATCH WITNESSES #(5)

This Corner established in Gladwin County Remonumentation Program.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-1: 3-4 SECTION CORNER ON TOWNSHIP LINE
SET 5/8"x36" RE-ROD WITH GLADWIN COUNTY RE-MON CAP, MARKED P.S. #9433 IN MON. BOX.

WITNESSES:
S45°E 53.05' - NAIL & TAG IN 16" BOX ELDER
SOUTH 55.00' - NAIL & TAG IN ASPHALT
N45°W 47.63' - NAIL & TAG IN POWER POLE
N.E. 47.55' - NAIL IN POWER POLE
WEST 29.95' - GLADWIN REMON G-13 T18N R2W
NORTH P.K. NAIL 2.0'
EAST P.K. NAIL 2.0'

APPROVED LAND CORNER

P.A. 345 of 1990
Gladwin County

Co. Rep. J. H. Meyers
Date 12/18/95

Signed by Paul B. Lapham
Surveyor's Michigan License No. 9433

Date 12-22-95

