

SURVEY &
REMONUMENTATION

JAN 17 1996

LAND CORNER RECORDATION CERTIFICATE
COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 61

For corners in

<u>GLADWIN</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T18N R 2W	H-1
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
GLADWIN COUNTY
FILED-REMONUMENTATION

26 DEC 95 10:47 A.M.

DONNIE K. HOUSE
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, PAUL B. LAPHAM, in a field survey on MAY-NOVEMBER, 19 95 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1856 GEO H. CANNON
SET POST
WIT.-(1)HEMLOCK 15" N72°E 9
(2)CEDAR 8" N36°W 20

1990 LAPHAM UNRECORDED L.C.R.C.
FOUND 1" IRON
WIT.-(7)N20°W POWER POLE NAIL 73.05'
(8)S25°W 4" PINE 61.00
(9)SOUTH C.I. 76.15'
(10)WEST 2" PIPE 31.35'

1979 LAPHAM L.C.R.C. #252
FOUND 1" PIPE
WIT.-(3)SOUTH FENCE COR. 29.30'
(4)N45°E 6" POST 41.55'
(5)N20°E POWER POLE 73.15'
(6)N45°W CORNER POST 39.65'

1980 LAPHAM SURVEY #G-802849
WIT.-SAME AS (3), (4), (5) & (6)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

NO COR. FOUND, SET PK NAIL FROM WITNESSES IN CENTER LINE ASPHALT ROAD OPPOSITE FENCE EAST, (7), (9) & (10) EXCAVATED NO COR. FOUND, SET GLADWIN RE-MON FROM WITNESSES.



This Corner established in Gladwin County Remonumentation Program.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-1: N 1/4 CORNER SECTION 3
SET 5/8"x36" RE-ROD WITH GLADWIN COUNTY RE-MON CAP IN MONUMENT BOX MARKED P.S. #9433.

WITNESSES:
N20°W 73.05' - NAIL & TAG IN POWER POLE
SOUTH 76.15' - SOUTH CAPPED IRON
WEST 31.35' - GLADWIN RE-MON CAP & IRON-CLOSING COR. H-13 T19N R2W
S05°W 34.40' - NAIL & TAG IN 6" SPRUCE
NORTH 2.0' P.K. NAIL
EAST 2.0' P.K. NAIL

APPROVED LAND CORNER
P.A. 345 of 1990
Gladwin County

Co. Rep. [Signature]
Date 12/18/95

Signed by Paul B. Lapham
Surveyor's Michigan License No. 9433

Date 12-22-95