

**SURVEY &  
MONUMENTATION**

JAN 17 1996

**COMMISSION LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>GLADWIN</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>18N</u> R <u>2W</u>	<u>1-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

USE 001 PAGE 66

STATE OF MICHIGAN  
GLADWIN COUNTY  
FILED-REMONUMENTATION

26 DEC 95 10:49 A.M.

DONNIE K. HOUSE  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, PAUL B. LAPHAM, in a field survey on MAY-NOVEMBER, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1856 GEO. H. CANNON  
SET POST  
WIT.-(1)ASPEN 12" N50°W 43  
(2)HEMLOCK S40°E 29

1989 LAPHAM SURVEY #G899031  
FOUND 2" PIPE  
WIT.-SAME AS (3), (4) & (5)

1975 LAPHAM L.C.R.C. #117  
FOUND 2" PIPE  
WIT.-(3)N80°E 35.95' 16" W. PINE  
(4)N85°E 34.12' FENCE POST  
(5)S30°E 71.90' TELE RISER

1990 LAPHAM UNRECORDED L.C.R.C. FOR COUNTY ROAD CONSTRUCTION  
FOUND 2 1/2" PIPE  
WIT.-(6)N30°E N&T 18" MAPLE 110.18'  
(7)S45°W 1/2"x36" RE-ROD 59.50'  
(8)N80°E N&T 16" W. PINE 36.25'  
(9)EAST N&T FENCE COR, 34.60'

1975 LAPHAM WORKING DWG.  
NO WITNESSES

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND SPIKE IN CENTER OF 2 1/2" PIPE, 1.5' BELOW SURFACE OF COUNTY ROAD, FENCE EAST & WEST EXCAVATED 3', DID NOT REMOVE 2 1/2" PIPE, SET GLADWIN RE-MON IN PIPE.



This Corner established in Gladwin County Remonumentation Program.  
See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1-7: CORNER COMMON TO SECTIONS 14, 15, 22 & 23  
SET 5/8"x36" RE-ROD WITH GLADWIN COUNTY RE-MON CAP, MARKED P.S. #9433 IN CENTER OF 2 1/2" PIPE.  
**APPROVED LAND CORNER**  
P.A. 345 of 1990  
Gladwin County

WITNESSES:  
N30°E 110.18' - NAIL & TAG IN 18" MAPLE  
S45°W 59.50' - 1/2"x36" RE-ROD  
N80°E 36.25' - NAIL & TAG IN 16" W. PINE  
EAST 34.60' - NAIL & TAG IN FENCE COR.

Co. Rep. J. H. Meyers  
Date 12/14/95

Signed by Paul B. Lapham  
Surveyor's Michigan License No. 9433

Date 12-27-95