

SURVEY & REMONUMENTATION

DEC 01 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE LIBER 001 PAGE 275
Filing Requirement of Act 74, Mich. P.A. 1970
Gladwin County Remonumentation

For Corners in
GLADWIN

(County)

Located In:

Corner Code#:

- | | | |
|--------------------------------------|-----------------------------|------------|
| 1. Public Land Survey | T. <u>18N</u> R. <u>02W</u> | <u>K-3</u> |
| | T. _____ R. _____ | _____ |
| | T. _____ R. _____ | _____ |
| 2. Public Controlling in Section | S. _____ T. _____ R. _____ | _____ |
| | S. _____ T. _____ R. _____ | _____ |
| 3. Miscellaneous Property in Section | S. _____ T. _____ R. _____ | _____ |
| | S. _____ T. _____ R. _____ | _____ |
| 4. Lot No. _____, Recorded Plat | | |
| 5. Private Claims | | |

STATE OF MICHIGAN
 GLADWIN COUNTY
 FILED-REMONUMENTATION

19 NOV 1999 2:02:43 PM

BONNIE K. HOUSE
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on April 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1856 Geo H. Cannon
 Wit-(1)Beech 12 S35E 28
 (2)Do 12 N40W 28

1938 MSHD field notes & road plans
 Axle Shaft
 Wit-(3)S58W Tel. Pole 53.82
 (4)N30W Tel. Pole 91.00
 (5)S60E Tel. Pole 54.78

1972 Lapham survey
 Wit-none

1975 Lapham
 LCRC#117, survey &
 work dwg
 Fd Monument Box
 Wit-none

1976-97 Lapham 7 surveys & work dwg
 Fd MSHD Mon Box in S lane
 8.95' E of C/L
 Wit-none

1998 MDOT
 Fd 1/2" Iron Rod in Mon Box
 See MDOT Plans#26011 for Loc and
 Wits

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found 1/2" Iron in Monument Box centerline county roads East & West, 8.95 feet East of centerline M-18. Iron agrees with MSHD 1938 and Lapham 1975 surveys. Also agrees with MDOT measurement to K-5 and 1938 MSHD field notes.

See dossier for detailed report.

APPROVED LAND CORNER
 P.A. 345 of 1990
 Gladwin County

Co. Rep. [Signature]
 Date 10/30/98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-3: Corner common to Sections 1, 2, 11 & 12. Set 5/8" x 18" reroed in Monument Box with Gladwin County Remonumentation Cap marked P.S.#27458.

Witnesses:

- S60°W Anchor Pole, nail & tag, 75.86'
- S60°E 4" x 4" Sign Post Cable Marker, nail & tag, 69.47' (MDOT)
- N60°E Power Pole, nail & tag, 73.81'
- N45°W 5" Spruce, nail & tag, 123.75'
- East, P.K. Nail, Centerline Bitumous Surface 89.50'
- N50°E Top Center R/W Marker 69.49'



Signed by Mark R. Robison
 Surveyor's Michigan License No. 27458

Date 11-16-99