

SURVEY & REMONUMENTATION

DEC 01 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970
 Gladwin County Remonumentation

LIBER 001 PAGE 276

For Corners in
GLADWIN

(County)

Located In:

Corner Code#:

- | | | |
|--------------------------------------|-----------------------------|------------|
| 1. Public Land Survey | T. <u>18N</u> R. <u>02W</u> | <u>K-4</u> |
| | T. _____ R. _____ | _____ |
| | T. _____ R. _____ | _____ |
| 2. Public Controlling in Section | S. _____ T. _____ | _____ |
| | S. _____ T. _____ | _____ |
| 3. Miscellaneous Property in Section | S. _____ T. _____ | _____ |
| | S. _____ T. _____ | _____ |
| 4. Lot No. _____, Recorded Plat | | _____ |
| 5. Private Claims | | _____ |

STATE OF MICHIGAN
 GLADWIN COUNTY
 FILED-REMONUMENTATION

19 NOV 1999 2:02:55 PM

BONNIE K. HOUSE
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Mark R. Robison, in a field survey on April 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1856 Geo H. Cannon

- 1976 Lapham survey
- Wit-(3) East 29.95 Fence Post
- (4) West 47.00 Power Pole
- (5) N30E 81.60 24" Maple

1987-90 Lapham
 2 surveys & work dwgs
 Wit-same as (3), (4) & (5)

1998 MDOT
 Set P.K. Nail for Cor by Lapham surveys
 See MDOT Plans#26011 for Loc & Wits

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found P.K. Nail 4 feet East of centerline, opposite property line to East.
 Nail agrees with witness (4) and Lapham and MDOT measurements to K-5 & K-3.

See dossier for detailed report.

APPROVED LAND CORNER
 P.A. 345 of 1990
 Gladwin County

Co. Rep. [Signature]
 Date 10-30-98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-4: 1/4 Corner common to Sections 11 & 12. Set 5/8" x 18" reroed in Monument Box with Gladwin County Remonumentation Cap marked P.S.#27458.

Witnesses:

- West Power Pole, nail & tag, 47.00'
- N30°E 30" Maple, nail & tag, 81.30' (MDOT)
- East Power Pole, nail & tag, 83.71' (MDOT)
- S15°E 12" Pine, nail & tag, 103.35' (MDOT)
- S50°E 14" Tree, nail & tag, 63.64'
- East 2" Pipe at Ground Level 43.57'
- S80°W Cluster 6" Oaks, nail & tag, 85.55'



Signed by Mark R. Robison
 Surveyor's Michigan License No. 27458

Date 11-16-99