

SURVEY & REMONUMENTATION

DEC 01 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Gladwin County Remonumentation

LIBER **001** PAGE **277**

SECTION

For Corners in
GLADWIN

(County)

Located In:

Corner Code#:

- 1. Public Land Survey T. 18N R. 02W K-5
 T. _____ R. _____
 T. _____ R. _____
- 2. Public Controlling in Section S. _____ T. _____ R. _____
 S. _____ T. _____ R. _____
- 3. Miscellaneous Property in Section S. _____ T. _____ R. _____
 S. _____ T. _____ R. _____
- 4. Lot No. _____ Recorded Plat _____
- 5. Private Claims _____

STATE OF MICHIGAN
 GLADWIN COUNTY
 FILED-REMONUMENTATION

19 NOV 1999 2:03:09 PM

BONNIE K. HOUSE
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on April 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

1856 Geo H. Cannon Old Corner
 Sections 11, 12, 13 & 14--Set Post
 Wit-(1)B. Ash 13 S16E 32
 (2) Do 11 N82W 14

1956 W.S. Moore survey
 Wit-(6)12" Oak N30W 99.6
 (7)12" Oak S50E 69.7

1938 MSHD field notes & road plans
 Axle Shaft
 Wit-(3)N62W Fe Cor Post 57.58
 (4)N39W Tel Pole 73.82
 (5)N60E Fe Cor Post 58.20

1974 Lapham LCRC#90 & survey
 Found 1 1/2" Bar in Mon Box
 Wit-(8)N75E 103.85 P.P.
 (9)N65W 85.80 P.P.
 (10)S60W 86.00 Cor Fe Post

1976-90 Lapham
 3 surveys & work dwgs
 Wit-same as (8), (9) & (10)

1998 MDOT
 Found 1 1/2" Bar in Mon Box
 See MDOT Plans#26011 for Loc & Wits

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found 1 1/2" Bar in Monument Box 1 foot East of centerline M-18, 5 feet North of centerline road to West, and 3 feet South of centerline road to East. Bar agrees with witnesses (8), (9) and (10). Also agrees with MSHD (1938), Moore (1956), Lapham (1974), and MDOT (1998) measurement to K-6.

See dossier for detailed report.

APPROVED LAND CORNER
P.A. 345 of 1990
Gladwin County

Co. Rep. [Signature]
 Date 10/30/98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-5: Corner common to Sections 11, 12, 13 & 14. Set 5/8" x 18" rered in Monument Box with Gladwin County Remonumentation Cap marked P.S.#27458.

- Witnesses:
- N65°W Power Pole, nail & tag, 85.76'
 - S60°W Fence Post, nail & tag, 86.11' (MDOT)
 - N75°E Power Pole, nail & tag, 103.70' (MDOT)
 - S55°E 4" x 4" Leg F.O.C. Marker, nail & tag, 74.23'
 - N45°E Top Center Nut on Gas Valve 77.27'
 - West 1/2" x 18" Rered 15' North of C/L road West 83.28'



Signed by [Signature]
 Surveyor's Michigan License No. 27458

Date 11-16-99